

Title (en)

Lifting of horizontally cast on-site wall panels

Title (de)

Heben von horizontal am Platz gegossenen Wandplatten

Title (fr)

Levage de panneaux de murs coulés horizontalement sur le chantier

Publication

**EP 1111143 A1 20010627 (EN)**

Application

**EP 99500255 A 19991229**

Priority

ES 9902834 A 19991223

Abstract (en)

These improvements consist in providing such pieces having means to ease moving thereof by ancillary means such as cranes and the like in such a way that moving, which involves hanging of the pieces, will not impair their resistant structure and will not impair the corresponding standardised profiles that serve as a frame of the pieces Stiffening the structure. Said means comprise a number of hooks distributed at the vertexes of the pieces and at the middle area of their major bases. Raising up of the pieces as well as moving thereof in a comfortable and effective way are made possible by means of the corresponding pulleys and IPN profiles without impairing the pieces. <IMAGE>

IPC 1-7

**E04B 1/35**; **B66C 1/12**

IPC 8 full level

**B66C 1/12** (2006.01); **E04B 1/35** (2006.01)

CPC (source: EP)

**B66C 1/12** (2013.01); **E04B 1/3505** (2013.01); **E04B 1/355** (2013.01)

Citation (search report)

[A] DE 2404025 A1 19750731 - MAIER ROLF DIPL ING

Cited by

CN110668301A

Designated contracting state (EPC)

DE FR IT PT

DOCDB simple family (publication)

**EP 1111143 A1 20010627**; **EP 1111143 B1 20051019**; DE 69927833 D1 20060302; DE 69927833 T2 20060706

DOCDB simple family (application)

**EP 99500255 A 19991229**; DE 69927833 T 19991229