

Title (en)

Method for producing pre-fabricated roof elements and facility for carrying out the method

Title (de)

Verfahren zur Herstellung von vorgefertigten Dachelementen und Anlage für deren Ausführung

Title (fr)

Procédé de fabrication d'éléments de toit préfabriqués et installation destinée à sa réalisation

Publication

EP 2299018 A3 20120404 (DE)

Application

EP 10174007 A 20100825

Priority

IT IT20090008 A 20090827

Abstract (en)

[origin: EP2299018A2] The method involves elaborating a roof element from fragmentation of a single module that is assembled by rectangular sides. Total length of a double module is formed by multiple partitions of discontinuous elements such as staves, skirting board, floor covering that are positioned on an outer side of a common rafter. An actual length of each module is supported over two slices that are spaced differently. A joining of the discontinuous elements coincides in different module. Tile support strap arrangements are aligned under the different modules.

IPC 8 full level

E04B 7/06 (2006.01); **E04B 7/20** (2006.01); **E04B 7/22** (2006.01)

CPC (source: EP)

E04B 7/063 (2013.01); **E04B 7/205** (2013.01); **E04B 7/225** (2013.01)

Citation (search report)

- [XY] US 5640812 A 19970624 - CROWLEY JOHN S [US], et al
- [X] DE 19743685 C1 19990211 - BRAAS GMBH [DE]
- [X] US 2004261356 A1 20041230 - WRASS LAWRENCE J [US]
- [IA] US 2007051067 A1 20070308 - WALL HARLIN [US]
- [Y] DE 2646533 A1 19780420 - LUX OSWALD

Designated contracting state (EPC)

AL AT BE BG CH CY CZ DE DK EE ES FI FR GB GR HR HU IE IS IT LI LT LU LV MC MK MT NL NO PL PT RO SE SI SK SM TR

Designated extension state (EPC)

BA ME RS

DOCDB simple family (publication)

EP 2299018 A2 20110323; EP 2299018 A3 20120404

DOCDB simple family (application)

EP 10174007 A 20100825