

Title (en)
Building construction module

Title (de)
Baumodul eines Gebäudes

Title (fr)
Module de construction de bâtiment

Publication
EP 2549025 B1 20150902 (FR)

Application
EP 12177010 A 20120719

Priority
FR 1156675 A 20110722

Abstract (en)
[origin: EP2549025A1] The module (10) has notches (11, 21, 31, 41) placed in lateral uprights (13, 23, 33, 43) to allow passage of pipes and distributed on the uprights on both sides of a horizontal symmetry axis (S). Two central notches, surrounding the axis of symmetry, are practiced, so that spacing (E) of the central notches corresponds to a standard spacing of forks of a fork lift truck. Intermediate uprights include notches aligned with the notches of the side uprights. The notches are partially closed again after the passage of the pipes.

IPC 8 full level
E04B 1/10 (2006.01); **E04B 2/74** (2006.01)

CPC (source: EP)
E04B 1/10 (2013.01); **E04B 2/7453** (2013.01); **E04B 2002/7488** (2013.01)

Cited by
EP3219865A1

Designated contracting state (EPC)
AL AT BE BG CH CY CZ DE DK EE ES FI FR GB GR HR HU IE IS IT LI LT LU LV MC MK MT NL NO PL PT RO RS SE SI SK SM TR

DOCDB simple family (publication)
EP 2549025 A1 20130123; **EP 2549025 B1 20150902**; ES 2554620 T3 20151222; FR 2978173 A1 20130125; FR 2978173 B1 20130816; PL 2549025 T3 20160429; PT 2549025 E 20151230

DOCDB simple family (application)
EP 12177010 A 20120719; ES 12177010 T 20120719; FR 1156675 A 20110722; PL 12177010 T 20120719; PT 12177010 T 20120719