



(12) **CORRECTED EUROPEAN PATENT SPECIFICATION**

(15) Correction information:  
**Corrected version no 1 (W1 B1)**  
**Corrections, see**  
**Claims EN 7**

(51) International Patent Classification (IPC):  
**C08B 37/00** <sup>(2006.01)</sup> **C40B 50/00** <sup>(2006.01)</sup>  
**A61K 47/00** <sup>(2006.01)</sup>

(48) Corrigendum issued on:  
**03.08.2022 Bulletin 2022/31**

(52) Cooperative Patent Classification (CPC):  
**A61K 9/0024; A61P 3/10; C08B 37/0084;**  
**A61K 9/5161**

(45) Date of publication and mention  
of the grant of the patent:  
**30.03.2022 Bulletin 2022/13**

(21) Application number: **18162427.1**

(22) Date of filing: **04.06.2012**

(54) **MODIFIED ALGINATES FOR CELL ENCAPSULATION AND CELL THERAPY**

MODIFIZIERTE ALGINATE FÜR ZELLVERKAPSELUNG UND ZELLTHERAPIE

ALGINATES MODIFIÉS POUR L'ENCAPSULATION CELLULAIRE ET LA THÉRAPIE CELLULAIRE

(84) Designated Contracting States:  
**AL AT BE BG CH CY CZ DE DK EE ES FI FR GB**  
**GR HR HU IE IS IT LI LT LU LV MC MK MT NL NO**  
**PL PT RO RS SE SI SK SM TR**

(30) Priority: **02.06.2011 US 201161492705 P**

(43) Date of publication of application:  
**01.08.2018 Bulletin 2018/31**

(60) Divisional application:  
**22165043.5**

(62) Document number(s) of the earlier application(s) in  
accordance with Art. 76 EPC:  
**12728887.6 / 2 714 747**

(73) Proprietors:  
• **Massachusetts Institute of Technology**  
**Cambridge, MA 02139 (US)**  
• **The Children's Medical Center Corporation**  
**Boston, MA 02115 (US)**

(72) Inventors:  
• **VEGAS, Arturo J**  
**Belmont, MA Massachusetts 02478 (US)**

• **MA, Minglin**  
**Ithaca, New York 14850 (US)**  
• **BRATLIE, Kaitlin M**  
**Ames, IA Iowa 50014 (US)**  
• **ANDERSON, Daniel G**  
**Framingham, MA Massachusetts 01701 (US)**  
• **LANGER, Robert S**  
**Newton, MA Massachusetts 02459 (US)**

(74) Representative: **Hoffmann Eitle**  
**Patent- und Rechtsanwälte PartmbB**  
**Arabellastraße 30**  
**81925 München (DE)**

(56) References cited:  
**EP-A1- 1 614 696 CN-A- 101 565 469**  
**GB-A- 768 309 US-A- 2 881 161**  
**US-A- 5 622 718 US-A1- 2008 242 738**

• **JI-SHENG YANG ET AL: "Research progress on**  
**chemical modification of alginate: A review",**  
**CARBOHYDRATE POLYMERS, vol. 84, no. 1, 1**  
**February 2011 (2011-02-01), pages 33-39,**  
**XP055035186, ISSN: 0144-8617, DOI:**  
**10.1016/j.carbpol.2010.11.048**

Note: Within nine months of the publication of the mention of the grant of the European patent in the European Patent Bulletin, any person may give notice to the European Patent Office of opposition to that patent, in accordance with the Implementing Regulations. Notice of opposition shall not be deemed to have been filed until the opposition fee has been paid. (Art. 99(1) European Patent Convention).

- VALLEE F ET AL: "Synthesis and rheological properties of hydrogels based on amphiphilic alginate-amide derivatives", CARBOHYDRATE RESEARCH, PERGAMON, GB, vol. 344, no. 2, 26 January 2009 (2009-01-26), pages 223-228, XP025838648, ISSN: 0008-6215, DOI: 10.1016/J.CARRES.2008.10.029 [retrieved on 2008-11-07]

**Description****FIELD OF THE INVENTION**

**[0001]** The present invention relates to the use of alginates, chemically modified to enhance their biocompatibility and tailor their physical properties, for the encapsulation of cells, particularly for the encapsulation of pancreatic islet cells, as well as methods of treating diseases or disorders, including diabetes, by implantation of the encapsulated cells.

**BACKGROUND OF THE INVENTION**

**[0002]** The transplantation of hormone- or protein-secreting cells from genetically non-identical members of the same species (*i.e.* allotransplantation) or from other species (*i.e.* xenotransplantation) is a promising strategy for the treatment of many diseases and disorders. Using alginate microcapsules to provide immunoisolation, hormone- or protein-secreting cells can be transplanted into a patient without the need for extensive treatment with immunosuppressant drugs. This principle has been successfully demonstrated by the transplantation of alginate-encapsulated pancreatic  $\beta$ -cells in diabetic rat models (Lim, F. and Sun, A. M. *Science*. 210, 908-910 (1980)). Methods of encapsulating biological material in alginate gels are described, for example, in U.S. Patent No. 4,352,883 to Lim. In the Lim process, an aqueous solution containing the biological materials to be encapsulated is suspended in a solution of a water soluble polymer. The suspension is formed into droplets which are configured into discrete microcapsules by contact with multivalent cations such as  $\text{Ca}^{2+}$ . The surface of the microcapsules is subsequently crosslinked with polyamino acids, forming a semipermeable membrane around the encapsulated materials.

**[0003]** The Lim method employs conditions which are mild enough to encapsulate cells without adversely affecting their subsequent survival and function. The resulting alginate microcapsules are semipermeable, possessing sufficient porosity to permit nutrients, waste, and the hormones and/or proteins secreted from encapsulated cells to diffuse freely into and out of the microcapsules, and, when implanted into an animal host, the alginate microcapsules effectively isolate the encapsulated cells from the host's immune system. See also United States Patent 7,807,150 to Vacanti, et al.

**[0004]** Many other synthetic materials have been tried, including block copolymers such as polyethyleneglycol-diacrylate polymers, polyacrylates, and thermoplastic polymers, as reported by U.S. Patent No. 6,129,761 to Hubbell and by Aebischer, et al, *J Biomech Eng.* 1991 May;113(2):178-83. See Lesney *Modern Drug Discovery* 4(3), 45-46, 49, 50 (2001) for review of these materials.

**[0005]** Since Lim first reported on the transplantation of encapsulated cells, many other have tried to create "bioreactors" for cells that could maintain viability of the cells in the absence of vascularization, by diffusion of nutrients, gases and wastes through the encapsulating materials, and still protect the cells from the body's immune defenses against foreign cells and materials. Unfortunately, efforts to translate these therapies into human subjects have proven difficult. For example, alginate-encapsulated porcine islet cells transplanted into a human subject suffering from Type 1 diabetes initially demonstrated significant improvement and required decreased insulin dosing. However, by week 49, the patient's insulin dose returned to pre-transplant levels (Elliot, R. B. et al. *Xenotransplantation*. 2007; 14(2): 157-161).

**[0006]** In some cases, it is desirable to elicit fibrosis, for example, when the cells are implanted as a bulking material, as described in U.S. Patent No. 6,060,053 and as subsequently approved by the Food and Drug Administration for treatment of vesicoureteral reflux.

**[0007]** The diminished efficacy of the implanted cells over time is the result of fibroblastic overgrowth of the alginate capsules. The alginate gel matrix provokes an inflammatory response upon implantation, resulting in the encapsulation of the alginate matrix with fibrous tissue. The fibrous tissue on the alginate capsule surface reduces the diffusion of nutrients and oxygen to the encapsulated cells, causing them to die. No better results have been obtained with the other materials.

**[0008]** Modified alginate polymers are disclosed by Yang et al, *Carbohydrate Polymers* 84(2011)33-39, US2008/0242738, GB768309, US 5 622 718, US2 881 161, and EP 1 614 696.

**[0009]** Therefore, it is an object of the invention to provide polymers suitable for encapsulation and implantation of cells where the polymers have greater long term biocompatibility following implantation.

**[0010]** It is another object of the present invention to provide chemically modified, ionically crosslinkable alginates with improved biocompatibility and tailored physiochemical properties, including gel stability, pore size, and hydrophobicity/hydrophilicity.


**[0011]** It is also an object of the invention to provide methods for the encapsulation of cells using modified alginate polymers.

**[0012]** Finally, it is an object of the invention to provide high-throughput methods for the characterization of modified alginate polymers.

## SUMMARY OF THE INVENTION

**[0013]** Alginates, chemically modified to tailor their biocompatibility and physical properties, have been developed. The modified alginates described herein provide enhanced properties relative to unmodified alginates. Moreover, based on the discovery that the starting materials, as well as chemically modified and reacted materials, must be exhaustively purified to remove contaminants prior to implantation to prevent encapsulation, these materials are less likely to elicit fibrous capsule formation following implantation.

**[0014]** Modified alginates are alginate polymers that contain one or more covalently modified monomers defined by Formula I



Formula I


wherein,

X is NR;

R<sub>1</sub> includes a 1,2,3-triazole ring or an alkyne group;

Y<sub>1</sub> and Y<sub>2</sub> independently are hydrogen or -PO(OR)<sub>2</sub>; or

Y<sub>2</sub> is absent, and Y<sub>1</sub>, together with the two oxygen atoms to which Y<sub>1</sub> and Y<sub>2</sub> are attached form a cyclic structure as shown below



and

R<sub>2</sub> and R<sub>3</sub> are, independently, hydrogen or an organic grouping containing any number of carbon atoms, preferably 1-30 carbon atoms, more preferably 1-20 carbon atoms, more preferably 1-14 carbon atoms, and optionally including one or more heteroatoms such as oxygen, sulfur, or nitrogen grouping in linear, branched, or cyclic structural formats, representative R groupings being alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, phenyl, substituted phenyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, alkoxy, substituted alkoxy, phenoxy, substituted phenoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, phenylthio, substituted phenylthio, arylthio, substituted arylthio, carbonyl, substituted carbonyl, carboxyl, substituted carboxyl, amino, substituted amino, amido, substituted amido, polyaryl, substituted polyaryl, C<sub>3</sub>-C<sub>20</sub> cyclic, substituted C<sub>3</sub>-C<sub>20</sub> cyclic, heterocyclic, substituted heterocyclic, aminoacid, poly(ethylene glycol), peptide, or polypeptide group; or

R<sub>2</sub> and R<sub>3</sub>, together with the carbon atom to which they are attached, form a 3- to 8-membered unsubstituted or substituted carbocyclic or heterocyclic ring; and

R is, independently for each occurrence, hydrogen or an organic grouping containing any number of carbon atoms,

preferably 1-30 carbon atoms, more preferably 1-20 carbon atoms, more preferably 1-14 carbon atoms, and optionally including one or more heteroatoms such as oxygen, sulfur, or nitrogen grouping in linear, branched, or cyclic structural formats, representative R groupings being alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, phenyl, substituted phenyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, alkoxy, substituted alkoxy, phenoxy, substituted phenoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, phenylthio, substituted phenylthio, arylthio, substituted arylthio, carbonyl, substituted carbonyl, carboxyl, substituted carboxyl, amino, substituted amino, amido, substituted amido, polyaryl, substituted polyaryl, C<sub>3</sub>-C<sub>20</sub> cyclic, substituted C<sub>3</sub>-C<sub>20</sub> cyclic, heterocyclic, substituted heterocyclic, aminoacid, poly(ethylene glycol), peptide, or polypeptide group.

**[0015]** Singularly modified alginate polymers are alginate polymers that contain one or more covalently modified monomers, wherein substantially all of the covalently modified monomers possess the same covalent modification (*i.e.* the polymer contains one 'type' or species of covalently modified monomer). Modified alginate polymers can contain any ratio of mannuronate monomers, guluronate monomers, and covalently modified monomers. In preferred embodiments, greater than 20%, more preferably greater than 25%, and most preferably greater than 30%, of the monomers in the modified alginate polymer are covalently modified monomers.

**[0016]** In preferred embodiments, the modified alginate polymer can be ionically crosslinked to form hydrogels using a polyvalent ion, such as Ca<sup>2+</sup>, Sr<sup>2+</sup>, or Ba<sup>2+</sup>. The ability of modified alginates to form stable hydrogels in physiological conditions can be quantified using the hydrogel formation assay described herein. In preferred embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput assay described herein is between 15,000 and 55,000, preferably between 20,000 and 55,000, more preferably between 25,000 and 55,000.

**[0017]** The modified alginate is biocompatible, and induces a lower foreign body response than unmodified alginate. The biocompatibility of modified alginates can be quantitatively determined using *in vitro* and *in vivo* assays known in the field, including the *in vivo* biocompatibility assay described herein. In preferred embodiments, the modified alginate polymer is biocompatible such that the fluorescence response normalized to unmodified alginate measured using the *in vivo* biocompatibility assay described herein is less than 75%, 70%, 65%, 60%, 55%, or 50%. Also described are assays for the characterization of modified alginate polymers.

**[0018]** A high throughput assay useful to characterize the ability of modified alginate polymers to form hydrogels is also described. In some embodiments, the hydrogel formation assay described herein is used to quantify the stability of hydrogels formed from alginates or modified alginates. In preferred embodiments, the hydrogel formation assay described herein is used as a screening tool to identify modified alginates capable of forming stable hydrogels. The high throughput *in vivo* biocompatibility assay described herein is used to identify modified alginates which induce a lower foreign body response than unmodified alginate. Assays are also provided for quantifying the biocompatibility of modified alginates.

**[0019]** Further described herein are methods of encapsulating biological materials using modified alginate polymers. In particular embodiments, the modified alginate polymers described herein are used to encapsulate cells for use in methods of treating a disease or disorder in a human or animal patient. In some embodiments, a disease or disorder in a human or animal patient is treated by transplanting exogenous biological material encapsulated in a modified alginate polymer. In particular embodiments, a disease or disorder in a human or animal patient is treated by transplanting cells encapsulated in a modified alginate polymer. In a more particular embodiment, diabetes is treated by transplanting pancreatic islet cells encapsulated in a modified alginate polymer.

## BRIEF DESCRIPTION OF THE DRAWINGS

### **[0020]**

Figure 1 shows the general structure of the modified alginates obtained using the combinatorial synthetic approach described in Example 1. The number of alginates prepared with each general structure is indicated below.

Figure 2 is a plot obtained from the hydrogel formation assay described in Example 2. The average fluorescence intensity values measured for modified alginates are plotted. Modified alginates yielding fluorescence values below 15,000 were considered unusable for applications where hydrogel formation is critical (*i.e.* the encapsulation of cells). Figure 3 is a plot showing the effect of selected modified alginates on HeLa cell line viability as compared to the positive control (no alginate). Alginate (Alg) has a viability of 53%. Several polymers are shown to be more cytotoxic than Alg, however, the majority of the library performs as well or better than Alg.



Figure 4 is a plot obtained using the *in vivo* method described in Example 5, which quantifies the biocompatibility of selected modified alginates. The fluorescence response obtained for the modified alginates using the *in vivo* method described in Example 5 was normalized to the fluorescence response measured using unmodified alginate in order to quantify the biocompatibility of the modified alginates in terms of % fluorescence response.

Figure 5 is a plot detailing the blood glucose level of mice transplanted with rat islets encapsulated in selected modified alginates as well as two different unmodified alginates (CMIT and CJOS). The dashed black line represents normoglycemia in mice.

Figure 6 is a bar graph showing inflammatory response (as measured by fluorescence normalized to VLVG) as a function of modified alginate (combined with unmodified alginate).

## DETAILED DESCRIPTION OF THE INVENTION

**[0021]** Alginates are a class of linear polysaccharide copolymers formed from 1-4-glycosidically linked  $\beta$ -D-mannuronate (M) and its C-5 epimer  $\alpha$ -L-guluronate (G). Alginates are naturally occurring biopolymers produced by a variety of organisms, including marine brown algae and at least two genera of bacteria (*Pseudomonas* and *Azotobacter*). Typically, commercial alginates are isolated from marine algae, including *Macrocystis pyrifera*, *Ascophyllum nodosum*, and various types of *Laminaria*.




**[0022]** Three types of primary structure define the polysaccharide backbone of alginates: homopolymeric regions of consecutive guluronate monomers (G-blocks), homopolymeric regions of consecutive mannuronate monomers (M-blocks), and regions containing alternating mannuronate and guluronate monomers (MG-blocks). The monomer blocks possess different conformations in solution, ranging from a flexible extended structure (M-blocks) to a rigid compact structure (G-blocks). In the case of G-blocks, the compact conformation facilitates the chelation of multivalent ions, notably  $\text{Ca}^{2+}$  ions, such that G-blocks in one alginate chain can be ionically crosslinked with G-blocks in another alginate chain, forming stable gels. As a result, the proportion, length, and distribution of the monomer blocks influence the physiochemical properties of the alginate polymer.

**[0023]** In the case of commercially produced alginates obtained from algae, the molecular weight, primary structure, and overall molar ratio of uronic acid monomers (M/G ratio) in the alginate polymer depends on a number of factors, including the species producing the alginate, the time of year in which the species is collected, and the location and age of the algal body. As a result, alginates possessing a range of physiochemical properties, such as molecular weight and viscosity, are commercially available.

**[0024]** Alginates can be ionically crosslinked at room temperature and neutral pH to form hydrogels. The ability of alginates to form stable gels in physiologically compatible conditions renders alginate gels useful in a number of biomedical applications. For example, alginate gels have been used as a matrix for drug delivery to modulate the pharmacokinetics of therapeutic, diagnostic, and prophylactic agents.

## I. Definitions

**[0025]** "Alginate", as used herein, is a collective term used to refer to linear polysaccharides formed from  $\beta$ -D-mannuronate and  $\alpha$ -L-guluronate in any M/G ratio, as well as salts and derivatives thereof. The term "alginate", as used herein, encompasses any polymer having the structure shown below, as well as salts thereof.



**[0026]** "Biocompatible", as used herein, refers to a material which performs its desired function when introduced into an organism without inducing significant inflammatory response, immunogenicity, or cytotoxicity to native cells, tissues, or organs. Biocompatibility, as used herein, can be quantified using the *in vivo* biocompatibility assay described herein in Example 5.


**[0027]** "Foreign Body Response", as used herein, refers to the immunological response of biological tissue to the presence of any foreign material in the tissue which can include protein adsorption, macrophages, multinucleated foreign body giant cells, fibroblasts, and angiogenesis.

**[0028]** "Chemically Modified Alginate" or "Modified Alginate", are used herein interchangeably, and refer to alginate polymers which contain one or more covalently modified monomers.

**[0029]** "Covalently Modified Monomer", as used herein, refers to a monomer which is an analog or derivative of a mannuronate and/or guluronate monomer obtained from a mannuronate and/or guluronate monomer via a chemical process.


**[0030]** "Singularly Modified Alginate Polymer", as used herein, refers to modified alginates that contain one or more covalently modified monomers, wherein substantially all of the covalently modified monomers possess the same covalent modification (*i.e.* the polymer contains one 'type' or species of covalently modified monomer). Singularly modified alginate polymers include, for example, modified alginate polymers wherein substantially all of the monomers in the modified alginate polymer are represented by mannuronate monomers, guluronate monomers, and a covalently modified monomer defined by Formula I. Not all of the monomers are necessarily covalently modified.

**[0031]** For clarity of discussion herein, singularly modified alginates are defined using formulae illustrating the structure of the covalently modified monomers incorporated in the backbone and omitting the mannuronate and guluronate monomers. For example, a singularly modified alginate polymer composed of mannuronate monomers, guluronate monomers, and a covalently modified monomer defined by Formula I, wherein X is NR,  $R_1$  is methyl, and R,  $Y_1$ , and  $Y_2$  are hydrogen, is illustrated herein by the structure below.




**[0032]** "Analog" and "Derivative" are used herein interchangeably, and refer to a compound having a structure similar to that of a parent compound, but varying from the parent compound by a difference in one or more certain components. Analogs or derivatives differ from the parent compound in one or more atoms, functional groups, or substructures, which are replaced with other atoms, groups, or substructures. An analog or derivative can be imagined to be formed, at least theoretically, from the parent compound via some chemical or physical process. The terms analog and derivative encompass compounds which retain the same basic ring structure as the parent compound, but possess one or more different substituents on the ring(s). For example, analog or derivative of mannuronate or guluronate refers to compounds which retain the core of the monomer, *e.g.*, the pyranose ring, but differ in one or more substituents on the ring.

**[0033]** "Mannuronate" and "Mannuronate Monomer", as used herein, refers to mannuronic acid monomers as well as salts thereof.



**[0034]** "Guluronate" and "Guluronate Monomer", as used herein, refers to guluronic acid monomers as well as salts thereof.



**[0035]** "Substantially", as used herein, specifies an amount of 95% or more, 96% or more, 97% or more, 98% or more, or 99% or more.

**[0036]** "Glass Transition Temperature" ( $T_g$ ), as used herein, refers to the temperature at which a reversible transition is observed in amorphous materials from a hard and relatively brittle state into a molten or rubber-like state.  $T_g$  values for alginate polymers can be experimentally determined using differential scanning calorimetry (DSC, heated and cooled at a rate of 10 K/min). In all cases herein, values of  $T_g$  are measured using powder polymer samples.

**[0037]** "Click Chemistry", as used herein, refers to chemical reactions used to couple two compounds together which are high yielding, wide in scope, create only byproducts that can be removed without chromatography, are stereospecific, simple to perform, and can be conducted in easily removable or benign solvents. Examples of reactions which fulfill these criteria include the nucleophilic ring opening of epoxides and aziridines, non-aldol type carbonyl reactions, including the formation of hydrazones and heterocycles, additions to carbon-carbon multiple bonds, including Michael Additions, and cycloaddition reactions, such as a 1,3-dipolar cycloaddition reaction (*i.e.* a Huisgen cycloaddition reaction). See, for example, Moses, J.E. and Moorhouse, A.D. Chem Soc. Rev. 2007; 36: 1249-1262; Kolb, H.C. and Sharpless, K.B. Drug Discovery Today. 2003; 8(24): 1128-1137; and Kolb, H.C., et al. Angew. Chem. Int. Ed. 2001; 40: 2004-2021.

**[0038]** "Polyvalent Cation", as used herein, refers to cations which have a positive charge greater than 1. Examples include, but are not limited to,  $\text{Ca}^{2+}$ ,  $\text{Ba}^{2+}$ , and  $\text{Sr}^{2+}$ .

**[0039]** "Substituted", as used herein, refers to all permissible substituents of the compounds or functional groups described herein. In the broadest sense, the permissible substituents include acyclic and cyclic, branched and unbranched, carbocyclic and heterocyclic, aromatic and nonaromatic substituents of organic compounds. Illustrative substituents include, but are not limited to, halogens, hydroxyl groups, or any other organic groupings containing any number of carbon atoms, preferably 1-14 carbon atoms, and optionally include one or more heteroatoms such as oxygen, sulfur, or nitrogen grouping in linear, branched, or cyclic structural formats. Representative substituents include alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, phenyl, substituted phenyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, halo, hydroxyl, alkoxy, substituted alkoxy, phenoxy, substituted phenoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, phenylthio, substituted phenylthio, arylthio, substituted arylthio, cyano, isocyano, substituted isocyano, carbonyl, substituted carbonyl, carboxyl, substituted carboxyl, amino, substituted amino, amido, substituted amido, sulfonyl, substituted sulfonyl, sulfonic acid, phosphoryl, substituted phosphoryl, phosphonyl, substituted phosphonyl, polyaryl, substituted polyaryl,  $\text{C}_3\text{-C}_{20}$  cyclic, substituted  $\text{C}_3\text{-C}_{20}$  cyclic, heterocyclic, substituted heterocyclic, aminoacid, peptide, and polypeptide groups.

**[0040]** Heteroatoms such as nitrogen may have hydrogen substituents and/or any permissible substituents of organic compounds described herein which satisfy the valences of the heteroatoms. It is understood that "substitution" or "substituted" includes the implicit proviso that such substitution is in accordance with permitted valence of the substituted atom and the substituent, and that the substitution results in a stable compound, *i.e.* a compound that does not spontaneously undergo transformation such as by rearrangement, cyclization, elimination, etc.

**[0041]** "Aryl", as used herein, refers to Cs-Cio-membered aromatic, heterocyclic, fused aromatic, fused heterocyclic, biaromatic, or biheterocyclic ring systems. Broadly defined, "aryl", as used herein, includes 5-, 6-, 7-, 8-, 9-, and 10-membered single-ring aromatic groups that may include from zero to four heteroatoms, for example, benzene, pyrrole, furan, thiophene, imidazole, oxazole, thiazole, triazole, pyrazole, pyridine, pyrazine, pyridazine and pyrimidine, and the like. Those aryl groups having heteroatoms in the ring structure may also be referred to as "aryl heterocycles" or "het-



eroaromatics". The aromatic ring can be substituted at one or more ring positions with one or more substituents including, but not limited to, halogen, azide, alkyl, aralkyl, alkenyl, alkynyl, cycloalkyl, hydroxyl, alkoxy, amino (or quaternized amino), nitro, sulfhydryl, imino, amido, phosphonate, phosphinate, carbonyl, carboxyl, silyl, ether, alkylthio, sulfonyl, sulfonamido, ketone, aldehyde, ester, heterocyclyl, aromatic or heteroaromatic moieties,  $-CF_3$ ,  $-CN$ ; and combinations thereof.


**[0042]** "Aryl" further encompasses polycyclic ring systems having two or more cyclic rings in which two or more carbons are common to two adjoining rings (i.e., "fused rings") wherein at least one of the rings is aromatic, e.g., the other cyclic ring or rings can be cycloalkyls, cycloalkenyls, cycloalkynyls, aryls and/or heterocycles. Examples of heterocyclic rings include, but are not limited to, benzimidazolyl, benzofuranyl, benzothiofuranyl, benzothiophenyl, benzoxazolyl, benzoxazolyl, benzthiazolyl, benztriazolyl, benztetrazolyl, benzisoxazolyl, benzisothiazolyl, benzimidazolyl, carbazolyl, 4aH carbazolyl, carbolinyl, chromanyl, chromenyl, cinnolinyl, decahydroquinolinyl, 2H,6H-1,5,2-dithiazinyl, dihydrofuro[2,3 b]tetrahydrofuran, furanyl, furazanyl, imidazolidinyl, imidazolyl, imidazolyl, 1H-indazolyl, indolenyl, indolyl, indolizyl, indolyl, 3H-indolyl, isatinoyl, isobenzofuranyl, isochromanyl, isoindazolyl, isoindolyl, isoindolyl, isoquinolinyl, isothiazolyl, isoxazolyl, methylenedioxyphenyl, morpholinyl, naphthyridinyl, octahydroisoquinolinyl, oxadiazolyl, 1,2,3-oxadiazolyl, 1,2,4-oxadiazolyl, 1,2,5-oxadiazolyl, 1,3,4-oxadiazolyl, oxazolidinyl, oxazolyl, oxindolyl, pyrimidinyl, phenanthridinyl, phenanthrolinyl, phenazinyl, phenothiazinyl, phenoxathinyl, phenoxazinyl, phthalazinyl, piperazinyl, piperidinyl, piperidonyl, 4-piperidonyl, piperonyl, pteridinyl, purinyl, pyranyl, pyrazinyl, pyrazolidinyl, pyrazolinyl, pyrazolyl, pyridazinyl, pyridooxazole, pyridoimidazole, pyridothiazole, pyridinyl, pyridyl, pyrimidinyl, pyrrolidinyl, pyrrolinyl, 2H-pyrrolyl, pyrrolyl, quinazolinyl, quinolinyl, 4H-quinolizyl, quinoxalyl, quinuclidinyl, tetrahydrofuran, tetrahydroisoquinolinyl, tetrahydroquinolinyl, tetrazolyl, 6H-1,2,5-thiadiazinyl, 1,2,3-thiadiazolyl, 1,2,4-thiadiazolyl, 1,2,5-thiadiazolyl, 1,3,4-thiadiazolyl, thianthrenyl, thiazolyl, thienyl, thienothiazolyl, thienooxazolyl, thienooxazolyl, thienoimidazolyl, thiophenyl and xanthenyl. One or more of the rings can be substituted as defined above for "aryl".

**[0043]** "Alkyl", as used herein, refers to the radical of saturated or unsaturated aliphatic groups, including straight-chain alkyl, alkenyl, or alkynyl groups, branched-chain alkyl, alkenyl, or alkynyl groups, cycloalkyl, cycloalkenyl, or cycloalkynyl (alicyclic) groups, alkyl substituted cycloalkyl, cycloalkenyl, or cycloalkynyl groups, and cycloalkyl substituted alkyl, alkenyl, or alkynyl groups. Unless otherwise indicated, a straight chain or branched chain alkyl has 30 or fewer carbon atoms in its backbone (e.g.,  $C_1$ - $C_{30}$  for straight chain,  $C_3$ - $C_{30}$  for branched chain), preferably 20 or fewer, more preferably 10 or fewer, most preferably 6 or fewer. If the alkyl is unsaturated, the alkyl chain generally has from 2-30 carbons in the chain, preferably from 2-20 carbons in the chain, more preferably from 2-10 carbons in the chain. Likewise, preferred cycloalkyls have from 3-20 carbon atoms in their ring structure, preferably from 3-10 carbons atoms in their ring structure, most preferably 5, 6 or 7 carbons in the ring structure.

**[0044]** The terms "alkenyl" and "alkynyl" refer to unsaturated aliphatic groups analogous in length and possible substitution to the alkyls described above, but that contain at least one double or triple bond respectively.

**[0045]** "Alkyl" includes one or more substitutions at one or more carbon atoms of the hydrocarbon radical as well as heteroalkyls. Suitable substituents include, but are not limited to, halogens, such as fluorine, chlorine, bromine, or iodine; hydroxyl;  $-NR_1R_2$ , wherein  $R_1$  and  $R_2$  are independently hydrogen, alkyl, or aryl, and wherein the nitrogen atom is optionally quaternized;  $-SR$ , wherein  $R$  is hydrogen, alkyl, or aryl;  $-CN$ ;  $-NO_2$ ;  $-COOH$ ; carboxylate;  $-COR$ ,  $-COOR$ , or  $-CONR_2$ , wherein  $R$  is hydrogen, alkyl, or aryl; azide, aralkyl, alkoxy, imino, phosphonate, phosphinate, silyl, ether, sulfonyl, sulfonamido, heterocyclyl, aromatic or heteroaromatic moieties,  $-CF_3$ ;  $-CN$ ;  $-NCOCOCH_2CH_2$ ;  $-NCOCOCHCH$ ;  $-NCS$ ; and combinations thereof.


**[0046]** "Amino" and "Amine", as used herein, are art-recognized and refer to both substituted and unsubstituted amines, e.g., a moiety that can be represented by the general formula:



wherein,  $R$ ,  $R'$ , and  $R''$  each independently represent a hydrogen, substituted or unsubstituted alkyl, substituted or unsubstituted alkenyl, substituted or unsubstituted alkynyl, substituted or unsubstituted carbonyl,  $-(CH_2)_m-R''$ , or  $R$  and  $R'$  taken together with the  $N$  atom to which they are attached complete a heterocycle having from 3 to 14 atoms in the ring structure;  $R''$  represents a hydroxy group, substituted or unsubstituted carbonyl group, an aryl, a cycloalkyl ring, a cycloalkenyl ring, a heterocycle, or a polycycle; and  $m$  is zero or an integer ranging from 1 to 8. In preferred embodiments, only one of  $R$  and  $R'$  can be a carbonyl, e.g.,  $R$  and  $R'$  together with the nitrogen do not form an imide. In preferred embodiments,  $R$  and  $R'$  (and optionally  $R''$ ) each independently represent a hydrogen atom, substituted or unsubstituted alkyl, a substituted or unsubstituted alkenyl, or  $-(CH_2)_m-R''$ . Thus, the term "alkylamine" as used herein refers to an amine group, as defined above, having a substituted or unsubstituted alkyl attached thereto (i.e. at least one of  $R$ ,  $R'$ , or  $R''$  is

an alkyl group).

**[0047]** "Carbonyl", as used herein, is art-recognized and includes such moieties as can be represented by the general formula:



wherein X is a bond, or represents an oxygen or a sulfur, and R represents a hydrogen, a substituted or unsubstituted alkyl, substituted or unsubstituted alkenyl, substituted or unsubstituted alkynyl,  $-(\text{CH}_2)_m\text{---R}''$ , or a pharmaceutical acceptable salt, R' represents a hydrogen, substituted or unsubstituted alkyl, substituted or unsubstituted alkenyl, substituted or unsubstituted alkynyl, or  $-(\text{CH}_2)_m\text{---R}''$ ; R'' represents a hydroxy group, substituted or unsubstituted carbonyl group, an aryl, a cycloalkyl ring, a cycloalkenyl ring, a heterocycle, or a polycycle; and m is zero or an integer ranging from 1 to 8. Where X is oxygen and R is defined as above, the moiety is also referred to as a carboxyl group. When X is oxygen and R is hydrogen, the formula represents a 'carboxylic acid'. Where X is oxygen and R' is hydrogen, the formula represents a 'formate'. In general, where the oxygen atom of the above formula is replaced by a sulfur, the formula represents a 'thiocarbonyl' group. Where X is sulfur and R or R' is not hydrogen, the formula represents a 'thioester'. Where X is sulfur and R is hydrogen, the formula represents a 'thiocarboxylic acid'. Where X is sulfur and R' is hydrogen, the formula represents a 'thioformate'. Where X is a bond and R is not hydrogen, the above formula represents a 'ketone'. Where X is a bond and R is hydrogen, the above formula represents an 'aldehyde'.

**[0048]** "Heteroalkyl", as used herein, refers to straight or branched chain, or cyclic carbon-containing radicals, or combinations thereof, containing at least one heteroatom. Suitable heteroatoms include, but are not limited to, O, N, Si, P and S, wherein the nitrogen, phosphorous and sulfur atoms are optionally oxidized, and the nitrogen heteroatom is optionally quaternized.

**[0049]** Examples of saturated hydrocarbon radicals include, but are not limited to, methyl, ethyl, n-propyl, isopropyl, n-butyl, t-butyl, isobutyl, sec-butyl, cyclohexyl, (cyclohexyl)methyl, cyclopropylmethyl, and homologs and isomers of, for example, n-pentyl, n-hexyl, n-heptyl, n-octyl. Examples of unsaturated alkyl groups include, but are not limited to, vinyl, 2-propenyl, crotyl, 2-isopentenyl, 2-(butadienyl), 2,4-pentadienyl, 3-(1,4-pentadienyl), ethynyl, 1- and 3-propynyl, and 3-butenyl.

**[0050]** "Alkoxy", "alkylamino", and "alkylthio" are used herein in their conventional sense, and refer to those alkyl groups attached to the remainder of the molecule via an oxygen atom, an amino group, or a sulfur atom, respectively.

**[0051]** "Alkylaryl", as used herein, refers to an alkyl group substituted with an aryl group (e.g., an aromatic or hetero aromatic group).

**[0052]** "Heterocycle" or "heterocyclic", as used herein, refers to a cyclic radical attached via a ring carbon or nitrogen of a monocyclic or bicyclic ring containing 3-10 ring atoms, and preferably from 5-6 ring atoms, consisting of carbon and one to four heteroatoms each selected from the group consisting of non-peroxide oxygen, sulfur, and N(Y) wherein Y is absent or is H, O, C<sub>1</sub>-C<sub>10</sub> alkyl, phenyl or benzyl, and optionally containing 1-3 double bonds and optionally substituted with one or more substituents. Examples of heterocyclic ring include, but are not limited to, benzimidazolyl, benzofuranyl, benzothiofuranyl, benzothiophenyl, benzoxazolyl, benzoxazolyl, benzthiazolyl, benztriazolyl, benztetrazolyl, benzisoxazolyl, benzisothiazolyl, benzimidazolyl, carbazolyl, 4aH-carbazolyl, carbolinyl, chromanyl, chromenyl, cinnolinyl, decahydroquinolinyl, 2H,6H-1,5,2-dithiazinyl, dihydrofuro[2,3-b]tetrahydrofuran, furanyl, furazanyl, imidazolidinyl, imidazolyl, imidazolyl, 1H-indazolyl, indolenyl, indolyl, indolizyl, indolyl, 3H-indolyl, isatinoyl, isobenzofuranyl, isochromanyl, isoindazolyl, isoindolyl, isoindolyl, isoquinolinyl, isothiazolyl, isoxazolyl, methylenedioxypheyl, morpholinyl, naphthyridinyl, octahydroisoquinolinyl, oxadiazolyl, 1,2,3-oxadiazolyl, 1,2,4-oxadiazolyl, 1,2,5-oxadiazolyl, 1,3,4-oxadiazolyl, oxazolidinyl, oxazolyl, oxindolyl, pyrimidinyl, phenanthridinyl, phenanthrolinyl, phenazinyl, phenothiazinyl, phenoxathinyl, phenoxazinyl, phthalazinyl, piperazinyl, piperidinyl, piperidonyl, 4-piperidonyl, piperonyl, pteridinyl, purinyl, pyranyl, pyrazinyl, pyrazolidinyl, pyrazolinyl, pyrazolyl, pyridazinyl, pyridooxazole, pyridoimidazole, pyridothiazole, pyridinyl, pyridyl, pyrimidinyl, pyrrolidinyl, pyrrolinyl, 2H-pyrrolyl, pyrrolyl, quinazolinyl, quinolinyl, 4H-quinolizyl, quinoxalyl, quinuclidinyl, tetrahydrofuranyl, tetrahydroisoquinolinyl, tetrahydroquinolinyl, tetrazolyl, 6H-1,2,5-thiadiazinyl, 1,2,3-thiadiazolyl, 1,2,4-thiadiazolyl, 1,2,5-thiadiazolyl, 1,3,4-thiadiazolyl, thianthrenyl, thiazolyl, thienyl, thienothiazolyl, thienooxazolyl, thienoimidazolyl, thiophenyl and xanthenyl. Heterocyclic groups can optionally be substituted with one or more substituents as defined above for alkyl and aryl.


**[0053]** "Halogen", as used herein, refers to fluorine, chlorine, bromine, or iodine.

## II. Modified Alginates

**[0054]** Described herein are alginate polymers that have been chemically modified to alter their biocompatibility and physical properties, as well as methods of making thereof.

## A. Structure of Modified Alginate Polymers

**[0055]** Modified alginates contain one or more covalently modified monomers defined by Formula I



Formula I


wherein,

X is NR;

R<sub>1</sub> includes a 1,2,3-triazole ring, or an alkyne group;

Y<sub>1</sub> and Y<sub>2</sub> independently are hydrogen or -PO(OR)<sub>2</sub>; or

Y<sub>2</sub> is absent, and Y<sub>2</sub>, together with the two oxygen atoms to which Y<sub>1</sub> and Y<sub>2</sub> are attached form a cyclic structure as shown below



wherein n is an integer between 1 and 4; and

R<sub>2</sub> and R<sub>3</sub> are, independently, hydrogen or an organic grouping containing any number of carbon atoms, preferably 1-30 carbon atoms, more preferably 1-20 carbon atoms, more preferably 1-14 carbon atoms, and optionally including one or more heteroatoms such as oxygen, sulfur, or nitrogen grouping in linear, branched, or cyclic structural formats, representative R groupings being alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, phenyl, substituted phenyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, alkoxy, substituted alkoxy, phenoxy, substituted phenoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, phenylthio, substituted phenylthio, arylthio, substituted arylthio, carbonyl, substituted carbonyl, carboxyl, substituted carboxyl, amino, substituted amino, amido, substituted amido, polyaryl, substituted polyaryl, C<sub>3</sub>-C<sub>20</sub> cyclic, substituted C<sub>3</sub>-C<sub>20</sub> cyclic, heterocyclic, substituted heterocyclic, aminoacid, poly(ethylene glycol), peptide, or polypeptide group; or

R<sub>2</sub> and R<sub>3</sub>, together with the carbon atom to which they are attached, form a 3- to 8-membered unsubstituted or substituted carbocyclic or heterocyclic ring; and

R is, independently for each occurrence, hydrogen or an organic grouping containing any number of carbon atoms, preferably 1-30 carbon atoms, more preferably 1-20 carbon atoms, more preferably 1-14 carbon atoms, and optionally including one or more heteroatoms such as oxygen, sulfur, or nitrogen grouping in linear, branched, or cyclic structural formats, representative R groupings being alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, phenyl, substituted phenyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, alkoxy, substituted alkoxy, phenoxy, substituted phenoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, phenylthio, substituted phenylthio, arylthio, substituted arylthio, carbonyl, substituted carbonyl, carboxyl, substituted carboxyl, amino,

substituted amino, amido, substituted amido, polyaryl, substituted polyaryl, C<sub>3</sub>-C<sub>20</sub> cyclic, substituted C<sub>3</sub>-C<sub>20</sub> cyclic, heterocyclic, substituted heterocyclic, aminoacid, poly(ethylene glycol), peptide, or polypeptide group.

**[0056]** The singularly modified alginate polymer contains one or more covalently modified monomers defined by Formula I, wherein R<sub>1</sub> includes an 1,2,3-triazole ring or an alkyne group

**[0057]** Modified alginate polymers can be of any desired molecular weight. The weight average molecular weight of the alginates is preferably between 1,000 and 1,000,000 Daltons, more preferably between 10,000 and 500,000 Daltons as determined by gel permeation chromatography.

**[0058]** Modified alginate polymers can contain any ratio of mannuronate monomers, guluronate monomers, and covalently modified monomers. In some embodiments, greater than 2.5%, 5%, 7.5%, 10%, 12%, 14%, 15%, 16%, 18%, 20%, 22%, 24%, 25%, 26%, 28%, 30%, 32.5%, 35%, 37.5%, 40%, 45%, 50%, 55%, or 60% of the monomers in the modified alginate polymer are covalently modified monomers. Preferably greater than 20%, more preferably greater than 25%, and most preferably greater than 30% of the monomers in the modified alginate polymer are covalently modified monomers.

**[0059]** Modified alginate polymers can be produced incorporating covalently modified monomers possessing a range of different hydrogen bonding potentials, hydrophobicities/hydrophilicities, and charge states. The inclusion of covalently modified monomers into an alginate polymer alters the physiochemical properties of alginate polymer. Accordingly, the physiochemical properties of alginates can be tuned for desired applications by the selective incorporation of covalently modified monomers.

**[0060]** For example, the glass transition temperature (T<sub>g</sub>), can be varied by the incorporation of covalently modified monomers. In some embodiments, the modified alginate polymer powder possess a T<sub>g</sub>, as measured by differential scanning calorimetry (DSC), of greater than 50°C, 60°C, 65°C, 70°C, 75°C, 80°C, 85°C, 90°C, 95°C, 100°C, 105°C, 110°C, 115°C, 120°C, 125°C, 130°C, 135°C, 140°C, 145°C, 150°C, 160°C, 175°C, 190°C, or 200°C.

**[0061]** The hydrophobicity/hydrophilicity of alginates can be varied by the incorporation of hydrophobic and/or hydrophilic covalently modified monomers. In preferred embodiments, the modified alginate polymer contains one or more hydrophobic covalently modified monomers. The relative hydrophobicity/hydrophilicity of modified alginates can be quantitatively assessed by measuring the contact angle of a water droplet on a film of the modified alginate polymer using a goniometer. In some embodiments, the modified alginate has a contact angle of less than 90° (*i.e.* it is hydrophilic). In preferred embodiments, the modified alginate has a contact angle of more than 90° (*i.e.* it is hydrophobic). In some embodiments, the modified alginate has a contact angle of more than 95°, 100°, 105°, 110°, 115°, or 120°.

**[0062]** In embodiments used for cell encapsulation, the modified alginate polymer can be ionically crosslinked by a polyvalent cation such as Ca<sup>2+</sup>, Sr<sup>2+</sup>, or Ba<sup>2+</sup> to form hydrogels. The ability of modified alginates to form stable hydrogels in physiological conditions can be quantified using the hydrogel formation assay described in Example 2.

**[0063]** In some embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput hydrogel formation assay described herein is greater than 10,000, 15,000, 20,000, 25,000, 30,000, 35,000, 40,000, 45,000, 50,000, or 55,000. In preferred embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput hydrogel formation assay described herein is greater than 15,000. In preferred embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput hydrogel formation assay described herein is between 15,000 and 55,000, preferably between 20,000 and 55,000, more preferably between 25,000 and 55,000.

**[0064]** In embodiments used for cell encapsulation, the modified alginate polymer forms a hydrogel with sufficient porosity to permit nutrients, waste, and the hormones and/or proteins secreted from encapsulated cells to diffuse freely into and out of the microcapsules, while simultaneously preventing the incursion of immune cells into the gel matrix. The porosity and surface area of modified alginate hydrogels can be measured using BET analysis. Prior to BET analysis, solvent and volatile impurities are removed by prolonged heating of the modified alginate gel under vacuum. Subsequently, the hydrogel samples are cooled under vacuum, for example by liquid nitrogen, and analyzed by measuring the volume of gas (typically N<sub>2</sub>, Kr, CO<sub>2</sub>, or Ar gas) adsorbed to the hydrogel at specific pressures. Analysis of the physisorption of the gas at variable pressures is used to characterize the total surface area and porosity of gels formed by the modified alginate polymers. The preferred method of determining hydrogel porosity is BET analysis.

**[0065]** In preferred embodiments, the modified alginate forms a hydrogel with sufficient porosity to permit nutrients, waste, and the hormones and/or proteins secreted from encapsulated cells to diffuse freely into and out of the microcapsules, while simultaneously preventing the incursion of immune cells into the gel matrix. In some embodiments, the porosity of the hydrogel formed by the modified alginate polymer is increased by 5%, 10%, 15%, or 20% relative to the porosity of a hydrogel formed from the unmodified alginate polymer. In alternative embodiments, the porosity of the hydrogel formed by the modified alginate polymer is decreased by 5%, 10%, 15%, or 20% relative to the porosity of a hydrogel formed from the unmodified alginate polymer. In preferred embodiments used for cell encapsulation, the modified alginate is biocompatible. The biocompatibility of modified alginates can be quantitatively determined using the fluorescence-based *in vivo* biocompatibility assay described in Example 5. In this assay, cathepsin activity was measured using

an *in vivo* fluorescence assay to quantify the foreign body response to the modified alginate.

[0066] In some embodiments, the modified alginate polymer is biocompatible such that the fluorescence response normalized to unmodified alginate measured using the *in vivo* biocompatibility assay described herein is less than 100%, 95%, 90%, 85%, 80%, 75%, 70%, 65%, 60%, 55%, 50%, 45%, or 40%. In preferred embodiments, the modified alginate polymer induces a lower foreign body response than unmodified alginate. This is indicated by fluorescence response normalized to unmodified alginate of less than 100%. In some embodiments, the modified alginate polymer is biocompatible such that the fluorescence response normalized to unmodified alginate measured using the *in vivo* biocompatibility assay described herein is less than 75%, more preferably less than 65%, and most preferably less than 50%.

## B. Particle Morphology

[0067] The growing recognition of the parameters driving fibrosis *in vivo* has been applied to the analysis of the performance of modified alginates. Intraperitoneal (IP) implantation of modified alginate capsules revealed that modified alginates may result in abnormally shaped capsules when crosslinked using conditions defined for unmodified alginates. These abnormally shaped capsules can complicate implementation and interpretation of modified alginate capsules implanted IP. In an effort to improve the capsule morphology, formulation methods for use with modified alginate micro-particles were developed where modified alginates were blended with a small amount of high molecular weight alginate. Particles prepared from this mixture yielded particles with improved morphology and stability.

[0068] The unmodified alginate typically has a weight average molecular weight of about 50,000 Daltons to about 500,000 Daltons; however, unmodified alginates having molecular weights can also be used. In some embodiments, the weight average molecular weight is from about 50,000 to about 250,000 Daltons, more preferably from about 50,000 to about 150,000 Daltons. In some embodiments, the weight average molecular weight is about 100,000 Daltons.

[0069] In other embodiments, one or more additional hydrogel-forming polymers are used in combination with unmodified alginate or in place of unmodified alginate. Such polymers are known in the art. Examples include, but are not limited to, PEG, chitosan, dextran, hyaluronic acid, silk, fibrin, poly(vinyl alcohol) and poly(hydroxyl ethyl methacrylate).


## C. Preparation of Modified Alginate Polymers

[0070] Modified alginates can be prepared through covalent modification of any available alginate polymer. Covalently modified monomers can be introduced into alginate polymers using a variety of synthetic procedures known in the art. In some embodiments, mannuronate and guluronate monomers are covalently modified via amidation of their carboxylic acid moiety. Stoichiometric variation of the reactants during covalent modification can be used to vary the amount of covalently modified monomer incorporated into the modified alginate.

[0071] In addition to the reactions discussed below, alternative synthetic methodologies for the covalent modification of mannuronate and guluronate monomers are known in the art. (see, for example, March, "Advanced Organic Chemistry," 5th Edition, 2001, Wiley-Interscience Publication, New York).


### 1. Modification via the Carboxylate Moiety of the Mannuronate and Guluronate Monomers

[0072] Mannuronate and guluronate monomers contain a carboxylic acid moiety which can serve as a point of covalent modification. In preferred embodiments, the carboxylic acid moiety present on one or more mannuronate and/or guluronate residues (1) are amidated as shown in Scheme 1.



Scheme 1. Representative Reaction Conditions: i. (reference only) HO-R<sub>1</sub>, 2-Chloro-4,6-dimethoxy-1,3,5-triazine (CDMT), N-methyl morpholine (NMM); ii. HNR<sub>1</sub>R<sub>2</sub>, CDMT, NMM.


**[0073]** Mannuronate and guluronate residues (A) can be covalently modified via amidation, forming modified monomer C. For example, mannuronate and guluronate residues (A) can be amidated by reaction with any suitable amine (R<sub>1</sub>-NH<sub>2</sub>) in the presence of a carbodiimide and DMAP. In a preferred method, mannuronate and guluronate residues (A) were amidated by reaction with a stoichiometric amount of a suitable amine (R<sub>1</sub>-NH<sub>2</sub>) in the presence of CDMT and NMM. Preferred amines for use as reagents in amidation reactions include those shown below.



## 2. Modification of Mannuronate and Guluronate Monomers via Click Chemistry

**[0074]** In some embodiments, mannuronate and guluronate monomers are covalently modified to introduce a functional group which can be further reacted via click chemistry.

**[0075]** In preferred embodiments, amidation is used to introduce a functional group which can further reacted using a 1,3-dipolar cycloaddition reaction (*i.e.* a Huisgen cycloaddition reaction). In a 1,3-dipolar cycloaddition reaction, a first molecule containing an azide moiety is reacted with a second molecule containing a terminal or internal alkyne. As shown below, the azide and the alkyne groups undergo an intramolecular 1,3-dipolar cycloaddition reaction, coupling the two molecules together and forming a 1,2,3-triazole ring.



**[0076]** The regiochemistry of 1,3-dipolar cycloadditions reaction can be controlled by addition of a copper(I) catalyst

(formed *in situ* by the reduction of  $CuSO_4$  with sodium ascorbate) or a ruthenium catalyst (such as  $Cp^*RuCl(PPh_3)_2$ ,  $Cp^*Ru(COD)$ , or  $Cp^*[RuCl_4]$ ). For example, using a copper catalyst, azides and terminal alkynes can be reacted to exclusively afford the 1,4-regioisomers of 1,2,3-triazoles. Similarly, in the presence of a suitable ruthenium catalyst, azides can be reacted with internal or terminal alkynes to form exclusively the 1,5-regioisomers of 1,2,3-triazoles.

**[0077]** In some embodiments, amidation is used to form a covalently modified monomer containing an alkyne moiety. In these embodiments, the alkyne moiety present on the covalently modified monomer can be further reacted with a second molecule containing an azide functional group. Upon reaction, the azide and the alkyne groups undergo an intramolecular 1,3-dipolar cycloaddition reaction forming a 1,2,3-triazole ring, coupling the second molecule to the covalently modified monomer.


**[0078]** In alternative embodiments, amidation is used to form a covalently modified monomer containing an azide moiety. In these embodiments, the azide moiety present on the covalently modified monomer can be further reacted with a second molecule containing a terminal or internal alkyne. Upon reaction, the azide and the alkyne groups undergo an intramolecular 1,3-dipolar cycloaddition reaction forming a 1,2,3-triazole ring, coupling the second molecule to the covalently modified monomer.

**[0079]** In preferred embodiments, amidation is used to form a covalently modified monomer containing an azide moiety. Subsequently, the azide moiety present on the covalently modified monomer is reacted with a second molecule containing a terminal or internal alkyne, forming a 1,2,3-triazole ring and coupling the second molecule to the covalently modified monomer.


**[0080]** As shown in Scheme 2, different strategies can be employed to prepare covalently modified monomers containing an azide moiety. For example, mannuronate and guluronate residues (A) can be amidated by reaction with an amine substituted with an azide moiety (for example, 11-Azido-3,6,9-trioxaundecan-1-amine) in the presence of a carbodiimide and DMAP, forming azide-functionalized modified monomer F in a single synthetic step. Alternatively, mannuronate and guluronate residues (A) can be amidated by reaction with an amine substituted with any moiety which can be readily transformed into an azide. For example, mannuronate and guluronate residues can be amidated by reaction with 4-iodobenzylamine in the presence of a carbodiimide and DMAP, forming iodo-functionalized monomer D. The iodine moiety can then be readily converted to the azide, for example by treatment with sodium azide.

**[0081]** Subsequently, the azide-functionalized monomers can be reacted with a molecule containing an alkyne functionality. For example, azide-functionalized monomers F and E can be reacted with a molecule containing a terminal alkyne functionality in the presence of a copper(I) catalyst (formed *in situ* by the reduction of  $CuSO_4$  with sodium ascorbate), forming covalently modified monomers G and H.


Scheme 2.



[0082] Preferred alkynes for use as reagents in 1,3-dipolarcycloaddition reactions include those shown below.








### 3. Modification via the Hydroxyl Moiety of the Mannuronate and Guluronate Monomers

**[0083]** Mannuronate and guluronate monomers contain hydroxyl moieties which can serve as a point of covalent modification. In preferred embodiments, the hydroxyl moieties of mannuronate and guluronate residues (1) are reacted as shown in Scheme 3.

Scheme 3.



**[0084]** Representative Reaction Conditions: i. I-PO(OR)<sub>2</sub>, pyridine; ii. R<sub>2</sub>-CO-R<sub>3</sub>, H<sup>+</sup>.

**[0085]** Mannuronate and guluronate residues (A) can be phosphorylated by a variety of methods known in the art, forming covalently modified monomer I. For example, mannuronate and guluronate residues can be phosphorylated by reaction with I-PO(OR)<sub>2</sub> in the presence of pyridine (Stowell, J. K. and Widlanski, T. S. Tetrahedron Lett. 1995; 36(11): 1825-1826.).

**[0086]** Mannuronate and guluronate residues (A) can also be converted to a cyclic acetal using procedures known in the art. For example, a cyclic acetal can be formed by reaction of mannuronate and guluronate residues with any suitable ketone (R<sub>2</sub>-CO-R<sub>3</sub>) in acidic conditions.

### C. Purification of Alginates

**[0087]** Commercial alginates are generally obtained from algae. Crude alginates from seaweed contain numerous contaminants, including polyphenols, proteins, and endotoxins (de Vos, P, et al. Biomaterials 2006; 27: 5603-5617). The presence of these impurities has been shown to limit the biocompatibility of implanted alginates.

**[0088]** To optimize the biocompatibility of the chemically modified alginates described herein, a rigorous purification methodology was developed to eliminate potentially irritating impurities. In preferred embodiments, ultra-pure low viscosity alginate (UPVLVG, FMC Biopolymer) was used as a substrate for covalent modification. Following each covalent modification, the modified alginates were filtered through modified silica columns, for example cyano-modified silica columns, aimed at capturing bulk organic impurities. Finally, after covalent modification of the alginate polymer is com-

plete, the modified alginates are dialyzed to remove any remaining small-molecule or low molecular weight impurities. In a preferred method, the modified alginates are dialyzed against 10,000 molecular weight cut-off (MWCO) membrane to remove any remaining small-molecule impurities.

[0089] The purity of the modified alginates can be determined by  $^1\text{H}$  NMR analysis. In such an analysis, the  $^1\text{H}$  NMR spectra of the modified alginate polymer is collected, and peaks corresponding to the modified alginate polymer and to any impurities are integrated to determine the relative quantity of each species in the sample. In some embodiments, the purity of the modified alginate polymer, as determined by  $^1\text{H}$  NMR, is greater than 90%, 91%, 92%, 93%, 94%, 95%, 96%, 97%, 98%, or 99%. In preferred embodiments, the purity of the modified alginate polymer, as determined by  $^1\text{H}$  NMR, is greater than 90%, more preferably greater than 95%.

### III. Assays for the Characterization of Modified Alginate Polymers

[0090] The covalent modification of alginate polymers alters the physiochemical properties and biological compatibility of the alginate polymer.

[0091] In some embodiments, a hydrogel formation assay is used to quantify the stability of hydrogels formed from alginates or modified alginates. In preferred embodiments, the hydrogel formation assay is used as a screening tool to identify modified alginates capable of forming stable hydrogels.

[0092] *In vivo* assays useful to characterize the biocompatibility of modified alginate polymers. In some embodiments, the high throughput *in vivo* biocompatibility assay described herein is used to identify modified alginates which induce a lower foreign body response than unmodified alginate.

[0093] Further described herein is an *in vivo* method for quantifying the biocompatibility of modified alginates.

[0094] The assays can be used to assess the suitability and biocompatibility of both modified and unmodified alginates for certain applications.

#### A. High Throughput Hydrogel Formation Assay

[0095] Covalent modification of the alginates affects the physical properties of the alginate, including the ability of the alginate to form hydrogels suitable for the encapsulation of cells and biomolecules.

[0096] The gel-forming assay exploits the ability of hydrogels to trap fluorescent compounds, and differentially retain the fluorophores upon washing based on the stability of the hydrogel. In this assay, a hydrogel formed by ionically crosslinking a candidate modified alginate in aqueous solution containing a dissolved fluorophore. A variety of fluorophores can be used in this assay. In preferred embodiments, the fluorophore possesses an emission maxima between 480 and 750 nm. In preferred embodiments, the fluorophore is a rhodamine dye possessing an emission maximum between 550 and 600 nm.

[0097] After crosslinking, the hydrogel is repeatedly washed with water. Candidate modified alginates which do not efficiently crosslink are washed away along with any fluorophore present. Modified alginates which efficiently crosslink retain the fluorophore during washes. Accordingly, by measuring the fluorescence of modified alginate hydrogels after washing, modified alginates capable of forming stable hydrogels can be readily identified.

[0098] In some embodiments, the relative fluorescence intensity values measured for a modified alginate are compared relative to fluorescence levels measured for the negative control and unmodified alginate to determine if the modified alginate is capable of forming hydrogels. In alternative embodiments, the hydrogel formation assay described herein is used to quantify the stability of hydrogels formed from alginates or modified alginates. In these embodiments, the fluorescence intensity measured for a modified alginate is used to indicate the stability of the hydrogel formed by the alginate.

[0099] In preferred embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput hydrogel formation assay described herein is greater than 10,000, 15,000, 20,000, 25,000, 30,000, 35,000, 40,000, 45,000, 50,000, or 55,000. In preferred embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput hydrogel formation assay described herein is greater than 15,000. In preferred embodiments, the modified alginate polymer forms hydrogels such that the fluorescence intensity measured using the high throughput hydrogel formation assay described herein is between 15,000 and 55,000, more preferably between 25,000 and 55,000.

#### B. High throughput *in vivo* biocompatibility assay

[0100] Current biocompatibility analysis methods are slow and require histological analysis. Described herein is a high throughput *in vivo* biocompatibility assay, useful for assessing the relative biocompatibility of alginate polymers.

[0101] In the high throughput *in vivo* biocompatibility assay described herein, modified alginate polymers and an unmodified alginate control are injected in an array format on the back of an animal test subject to facilitate high-throughput

screening. In preferred embodiments, the animal test subject is a mouse. After injection, cathepsin activity at the point of injection of the modified alginates was compared to cathepsin activity at the point of injection the unmodified alginate to compare the foreign body response to the implanted alginates using *in vivo* fluorescence imaging. In preferred embodiments, the biocompatibility of the materials was assessed at 14 days post injection using *in vivo* fluorescence imaging.

[0102] In preferred embodiments, the high throughput *in vivo* biocompatibility assay described herein is used to identify modified alginates which induce a lower foreign body response than unmodified alginate. The fluorescence intensity measured at the implantation site of modified alginates was compared with the fluorescence intensity measured at the implantation site of an unmodified alginate. In preferred embodiments, modified alginates exhibiting a smaller fluorescence intensity at the implantation site than the fluorescence intensity measured at the implantation site of an unmodified alginates were qualitatively characterized as biocompatible. Conversely, modified alginates exhibiting a greater fluorescence intensity at the implantation site than the fluorescence intensity measured at the implantation site of an unmodified alginates were characterized as not biocompatible.

[0103] The high throughput *in vivo* biocompatibility assay described above can also be used to characterize the ability of modified alginates to form mechanically stable hydrogels *in vivo*. In preferred embodiments, the *in vivo* stability of the alginate gels was assessed at 28 days post injection.

[0104] In preferred embodiments, modified alginates gels which remained at the site of injection after 28 days were characterized as capable of forming mechanically stable hydrogels *in vivo*. Conversely, modified alginate gels which were not present at the site of injection after 28 days were deemed to not capable of forming mechanically stable hydrogels *in vivo*.

### C. *In vivo* screening of modified alginates to quantify biocompatibility

[0105] Further described herein is an *in vivo* method for quantifying the biocompatibility of modified alginates.

[0106] In this method, a modified alginate polymers is injected on the back of an animal test subject. In preferred embodiments, the animal test subject is a mouse. After injection, cathepsin activity at the point of injection of the modified alginates was measured using *in vivo* fluorescence assay. In preferred embodiments, the fluorescence assay was conducted at at 7 days post injection using *in vivo* fluorescence imaging. In preferred embodiments, the fluorescence intensity was measured and normalized to the fluorescence response measured using unmodified alginate in order to quantify the biocompatibility of the modified alginates.

[0107] In preferred embodiments, the modified alginate polymer induces a lower foreign body response than unmodified alginate (*i.e.* the fluorescence response normalized to unmodified alginate is less than 100%). In some embodiments, the modified alginate polymer is biocompatible such that the fluorescence response normalized to unmodified alginate measured using the *in vivo* biocompatibility assay described herein is less than 95%, 90%, 85%, 80%, 75%, 70%, 65%, 60%, 55%, 50%, 45%, or 40%. In preferred embodiments, the modified alginate polymer is biocompatible such that the fluorescence response normalized to unmodified alginate measured using the *in vivo* biocompatibility assay described herein is less than 75%, more preferably less than 65%, and most preferably less than 50%.

## IV. Methods of Use

[0108] Alginates are used in a variety of applications in the food, pharmaceutical, cosmetic, agriculture, printing, and textile industries. Alginates are widely employed in the food industry as thickening, gelling, stabilizing, bodying, suspending, and emulsifying agents. Alginates can be used as a matrix to control the delivery of therapeutic, prophylactic, and/or diagnostic agents. Alginates can be incorporated in pharmaceutical compositions as excipients, where they can act as viscosifiers, suspension agents, emulsifiers, binders, and disintegrants. Alginate also used as a dental impression material, component of wound dressings, and as a printing agent. One of ordinary skill in the art will recognize that the modified alginates disclosed herein can be used in any application for which alginates are currently employed.

[0109] It is specifically contemplated that modified alginates described herein can be used in applications where improved biocompatibility and physical properties, as compared to commercially available alginates, are preferred.

### A. Encapsulation of Cells

[0110] Alginate can be ionically cross-linked with divalent cations, in water, at room temperature, to form a hydrogel matrix. See, for example, in U.S. Patent No. 4,352,883 to Lim. In the Lim process, an aqueous solution containing the biological materials to be encapsulated is suspended in a solution of a water soluble polymer, the suspension is formed into droplets which are configured into discrete microcapsules by contact with multivalent cations, then the surface of the microcapsules is crosslinked with polyamino acids to form a semipermeable membrane around the encapsulated materials.

[0111] The water soluble polymer with charged side groups is crosslinked by reacting the polymer with an aqueous

solution containing multivalent ions of the opposite charge, either multivalent cations if the polymer has acidic side groups or multivalent anions if the polymer has basic side groups. The preferred cations for cross-linking of the polymers with acidic side groups to form a hydrogel are divalent and trivalent cations such as copper, calcium, aluminum, magnesium, strontium, barium, and tin, although di-, tri- or tetra-functional organic cations such as alkylammonium salts, e.g.,  $R_3N^+--\backslash \Delta \Delta /---NR_3$  can also be used. Aqueous solutions of the salts of these cations are added to the polymers to form soft, highly swollen hydrogels and membranes. The higher the concentration of cation, or the higher the valence, the greater the degree of cross-linking of the polymer. Concentrations from as low as 0.005 M have been demonstrated to cross-link the polymer. Higher concentrations are limited by the solubility of the salt.

**[0112]** The preferred anions for cross-linking of polymers containing basic sidechains to form a hydrogel are divalent and trivalent anions such as low molecular weight dicarboxylic acids, for example, terephthalic acid, sulfate ions and carbonate ions. Aqueous solutions of the salts of these anions are added to the polymers to form soft, highly swollen hydrogels and membranes, as described with respect to cations.

**[0113]** A variety of polycations can be used to complex and thereby stabilize the polymer hydrogel into a semi-permeable surface membrane. Examples of materials that can be used include polymers having basic reactive groups such as amine or imine groups, having a preferred molecular weight between 3,000 and 100,000, such as polyethylenimine and polylysine. These are commercially available. One polycation is poly(L-lysine); examples of synthetic polyamines are: polyethylenimine, poly(vinylamine), and poly(allyl amine). There are also natural polycations such as the polysaccharide, chitosan.

**[0114]** Polyanions that can be used to form a semi-permeable membrane by reaction with basic surface groups on the polymer hydrogel include polymers and copolymers of acrylic acid, methacrylic acid, and other derivatives of acrylic acid, polymers with pendant  $SO_3H$  groups such as sulfonated polystyrene, and polystyrene with carboxylic acid groups.

**[0115]** In a preferred method, cells are encapsulated in a modified alginate polymer. In a preferred embodiment, modified alginate capsules are fabricated from solution of modified alginate containing suspended cells using the encapsulator (such as an Inotech encapsulator). In some embodiments, modified alginate are ionically crosslinked with a polyvalent cation, such as  $Ca^{2+}$ ,  $Ba^{2+}$ , or  $Sr^{2+}$ . In particularly preferred embodiments, the modified alginate is crosslinked using  $BaCl_2$ . In some embodiments, the capsules are further purified after formation. In preferred embodiments, the capsules are washed with, for example, HEPES solution, Krebs solution, and/ or RPMI-1640 medium.

**[0116]** Cells can be obtained directed from a donor, from cell culture of cells from a donor, or from established cell culture lines. In the preferred embodiments, cells are obtained directly from a donor, washed and implanted directly in combination with the polymeric material. The cells are cultured using techniques known to those skilled in the art of tissue culture. In the preferred embodiment, the cells are autologous - i.e., derived from the individual into which the cells are to be transplanted, but may be allogeneic or heterologous.

**[0117]** Cell attachment and viability can be assessed using scanning electron microscopy, histology, and quantitative assessment with radioisotopes. The function of the implanted cells can be determined using a combination of the above-techniques and functional assays. For example, in the case of hepatocytes, in vivo liver function studies can be performed by placing a cannula into the recipient's common bile duct. Bile can then be collected in increments. Bile pigments can be analyzed by high pressure liquid chromatography looking for underivatized tetrapyrroles or by thin layer chromatography after being converted to azodipyrroles by reaction with diazotized azodipyrroles ethylantranilate either with or without treatment with P-glucuronidase. Diconjugated and monoconjugated bilirubin can also be determined by thin layer chromatography after alkalinemethanolysis of conjugated bile pigments. In general, as the number of functioning transplanted hepatocytes increases, the levels of conjugated bilirubin will increase. Simple liver function tests can also be done on blood samples, such as albumin production. Analogous organ function studies can be conducted using techniques known to those skilled in the art, as required to determine the extent of cell function after implantation. For example, islet cells of the pancreas may be delivered in a similar fashion to that specifically used to implant hepatocytes, to achieve glucose regulation by appropriate secretion of insulin to cure diabetes. Other endocrine tissues can also be implanted. Studies using labeled glucose as well as studies using protein assays can be performed to quantitate cell mass on the polymer scaffolds. These studies of cell mass can then be correlated with cell functional studies to determine what the appropriate cell mass is. In the case of chondrocytes, function is defined as providing appropriate structural support for the surrounding attached tissues.

**[0118]** This technique can be used to provide multiple cell types, including genetically altered cells, within a three-dimensional scaffolding for the efficient transfer of large number of cells and the promotion of transplant engraftment for the purpose of creating a new tissue or tissue equivalent. It can also be used for immunoprotection of cell transplants while a new tissue or tissue equivalent is growing by excluding the host immune system.

**[0119]** Examples of cells which can be implanted as described herein include chondrocytes and other cells that form cartilage, osteoblasts and other cells that form bone, muscle cells, fibroblasts, and organ cells. As used herein, "organ cells" includes hepatocytes, islet cells, cells of intestinal origin, cells derived from the kidney, and other cells acting primarily to synthesize and secrete, or to metabolize materials. A preferred cell type is a pancreatic islet cell.

**[0120]** The polymeric matrix can be combined with humoral factors to promote cell transplantation and engraftment.

For example, the polymeric matrix can be combined with angiogenic factors, antibiotics, antiinflammatories, growth factors, compounds which induce differentiation, and other factors which are known to those skilled in the art of cell culture.

[0121] For example, humoral factors could be mixed in a slow-release form with the cell-alginate suspension prior to formation of implant or transplantation. Alternatively, the hydrogel could be modified to bind humoral factors or signal recognition sequences prior to combination with isolated cell suspension.

[0122] The techniques described herein can be used for delivery of many different cell types to achieve different tissue structures. In the preferred embodiment, the cells are mixed with the hydrogel solution and injected directly into a site where it is desired to implant the cells, prior to hardening of the hydrogel. However, the matrix may also be molded and implanted in one or more different areas of the body to suit a particular application. This application is particularly relevant where a specific structural design is desired or where the area into which the cells are to be implanted lacks specific structure or support to facilitate growth and proliferation of the cells.

[0123] The site, or sites, where cells are to be implanted is determined based on individual need, as is the requisite number of cells. For cells having organ function, for example, hepatocytes or islet cells, the mixture can be injected into the mesentery, subcutaneous tissue, retroperitoneum, peritoneal space, and intramuscular space. For formation of cartilage, the cells are injected into the site where cartilage formation is desired. One could also apply an external mold to shape the injected solution. Additionally, by controlling the rate of polymerization, it is possible to mold the cell-hydrogel injected implant like one would mold clay. Alternatively, the mixture can be injected into a mold, the hydrogel allowed to harden, then the material implanted.

## B. Treatment of Diseases or Disorders

[0124] Encapsulated cells can be transplanted into a patient in need thereof to treat a disease or disorder. In some embodiments, the encapsulated cells are obtained from a genetically non-identical member of the same species. In alternative embodiments, the encapsulated cells are obtained from a different species than the patient. In preferred embodiments, hormone- or protein-secreting cells are encapsulated and transplanted into a patient to treat a disease or disorder.

[0125] In preferred embodiments, the disease or disorder is caused by or involves the malfunction hormone- or protein-secreting cells in a patient. In a preferred embodiment, the disease or disorder is diabetes.

[0126] The present invention will be further understood by reference to the following non-limiting examples.

### Examples

#### Example 1: Combinatorial synthesis of chemically modified alginates (Reference only)


[0127] The determinate parameters governing material biocompatibility are poorly understood. Accordingly, the rational design and synthesis of modified alginates possessing improved biocompatibility is challenging. In an effort to identify modified alginates with improved biocompatibility and physical properties, a combinatorial approach was used to prepare a library of modified alginates possessing a range of covalent modifications.


##### 1. General Combinatorial Strategy

[0128] A pool of twelve alcohols, nine amines, two amines used to introduce an azide moiety (one amine containing an azide moiety and one amine containing an iodide moiety to be converted to an azide moiety subsequent to amidation), and nineteen alkynes with a range of different chemical structures, hydrophobicities/hydrophilicities, hydrogen-bonding potentials, and charge states were selected as reagents for the combinatorial synthesis of modified alginates. With the knowledge that impurities present in alginate polymers have been shown to limit the biocompatibility of implanted alginates, ultra-pure, low viscosity alginate (UPLVG, FMC Biopolymers) was selected as a starting material for modification experiments.


##### Alcohols Used as Reagents for Esterification

[0129]





5




10


### Amines used as Reagents for Amidation

**[0130]**


15



20




25



### 30 Amines used as Reagents to Introduce Azide Moieties

**[0131]**


35




### Alkynes Used as Reagents for 1,3-Dipolar Cycloaddition

**[0132]**

40



55



15 **[0133]** Unmodified alginate polymer was covalently modified by reaction with one, two, or three the esters, amines, and/or alkynes shown above in a combinatorial fashion. Figure 1 shows the general structure of the modified alginates obtained using this method.

## 2. Representative Reaction Conditions

20 **[0134]** Due to the parallel and combinatorial nature of the modification process, synthetic reactions were performed using a robotic core module. UPLVG alginate was selected as a starting material for modification experiments. In the first combinatorial reaction, the unmodified alginate was reacted with one of the alcohols, amines, and amines used to introduce an azide moiety in the presence of 2-Chloro-4,6-dimethoxy-1,3,5-triazine (CDMT) and N-methyl morpholine (NMM). In a second combinatorial step, each of the modified alginate polymers formed above was reacted with another  
25 of the alcohols, amines, or amines used to introduce an azide moiety in the presence of 2-Chloro-4,6-dimethoxy-1,3,5-triazine (CDMT) and N-methyl morpholine (NMM). In a final combinatorial step, all members of the library which were reacted with an amine used to introduce an azide moiety were further functionalized using a 1,3-dipolar cycloaddition reaction. Those members of the library which had been reacted with 4-iodobenzylamine were first reacted with sodium azide to convert the iodide moieties to azide moieties. Subsequently, all members of the library which were reacted with  
30 an amine used to introduce an azide moiety were reacted with one of the alkynes used as reagents for 1,3-dipolar cycloaddition in the presence of  $\text{CuSO}_4$ /sodium ascorbate.

**[0135]** To optimize the biocompatibility of the chemically modified alginates, a rigorous purification methodology was developed to eliminate potentially irritating impurities. Following each covalent modification, the modified alginates were filtered through a cyano-modified silica column aimed at capturing bulk organic impurities. Finally, after completing all  
35 covalent modification steps, the modified alginates were dialyzed against 10,000 MWCO membrane to remove any remaining small-molecule or low molecular weight impurities.

**[0136]** The purity of the modified alginates was determined by  $^1\text{H}$  NMR analysis. The  $^1\text{H}$  NMR spectra of each modified alginate polymer was collected, and peaks corresponding to the modified alginate polymer and to any impurities were integrated to determine the relative quantity of each species in the sample.  
40

## Example 2: High throughput screening of modified alginates using a hydrogel formation assay (Reference only)

**[0137]** Covalent modification of the alginates affects the physical properties of the alginate, including the ability of the alginate to form hydrogels suitable for the encapsulation of cells and biomolecules. To eliminate modified alginates that  
45 have lost their ability to form hydrogels and to further focus our screening efforts on stronger candidates, a fluorescence-based crosslinking assay was used to quantify the ability of modified alginates to form hydrogels.

**[0138]** The hydrogel formation assay described herein exploits the ability of hydrogels to trap fluorescent compounds, and differentially retain the fluorophores upon washing based on the stability of the hydrogel. Each of the modified alginates prepared using the combinatorial approach described in Example 1 was dissolved in water. A rhodamine dye that fluoresces at 580 nm was added to each sample. The modified alginate sample was then crosslinked by the addition  
50 of a barium or calcium salt, for example  $\text{BaCl}_2$ , to induce formation of a hydrogel. After incubation for 10 minutes, each sample was washed repeatedly with water. The fluorescence intensity of each sample was measured using a fluorimeter.

**[0139]** Each modified alginate was screened three times, and the results obtained in the three trials were averaged. The average fluorescence intensity values for each modified alginate were compared to the fluorescence levels of the negative control (water) and unmodified alginate (UPLVG). Modified alginates yielding fluorescence values below the  
55 negative control were considered unusable for applications where hydrogel formation is critical (*i.e.* the encapsulation of cells).

**Example 3: *In vitro* screening of modified alginates for biocompatibility (Reference only)**

**[0140]** The cytotoxicity of the modified alginate polymers on HeLa cells was evaluated to screen for biocompatibility *in vitro*. The modified alginates identified in Example 2 as capable of forming hydrogels were loaded into wells of 96-well plates which were coated with poly-L-lysine. Unmodified alginate and saline were also loaded into wells of 96-well plates which were coated with poly-L-lysine as controls. A 100mM BaCh crosslinking solution was dispensed in all of the wells of the 96-well plate. The excess crosslinker was then aspirated. HeLa cells were seeded into the wells and incubated for 3 days at 37°C in a humidified chamber.

**[0141]** A cell viability assay using 3-(4,5-Dimethylthiazol-2-yl)-2,5-diphenyltetrazolium bromide (MTT) was performed, in which the media was aspirated from all wells and 100µl of DMEM media without phenol red and 10µl MTT (5mg/ml) were added to all of the wells of the 96-well plate. The plate was incubated for 4 hours at 37°C in a humidified chamber. After incubation, 85µl of solution was aspirated and 100µl DMSO was added. Purple formazan crystals form during the assay in proportion to the number of viable HeLa cells present in each well. The contents of each well were pipetted up and down to solubilize the formazan crystals prior to measurement. The plate was incubated at 37°C for 10 minutes after which the bubbles from agitation were removed. The plate was read using a UV/Vis plate reader at 540nm with a reference at 700nm. The viability was normalized to cells seeded in wells with no alginate.

**[0142]** The results of the cell viability are shown in Figure 3, which plots the effect of selected modified alginates on HeLa cell line viability as compared to the positive control (no alginate). Alginate (Alg) has a viability of 53%. The assay identified modified alginate polymers which displayed decreased cytotoxicity relative to unmodified alginate. These were selected for further analysis.

**Example 4: High throughput *in vivo* screening of modified alginates to assess biocompatibility**

**[0143]** Current biocompatibility analysis methods are slow and require histological analysis. In order to screen the large numbers of modified alginates prepared using the combinatorial synthetic methods described herein, a high throughput *in vivo* biocompatibility assay was used to assess the relative biocompatibility of alginate polymers.

**1. High throughput *in vivo* screening protocol**

**[0144]** 8-12 week old male SKH1 mice were obtained from Charles River Laboratories (Wilmington, MA). The mice were maintained at the animal facilities of Massachusetts Institute of Technology, accredited by the American Association of Laboratory Animal care, and were housed under standard conditions with a 12-hour light/dark cycle. Both water and food were provided *ad libitum*.

**[0145]** Injections were performed in accordance with ISO 10993-6: 2001. Prior to injection all materials were sterilized via 0.22 µm filtration. The mice were anesthetized via isoflurane inhalation at a concentration of 1-4% isoflurane/balance O<sub>2</sub> to minimize movement. Their backs were scrubbed with 70% isopropyl alcohol and the animals were injected with modified alginates in an array format on the mouse's back for high-throughput screening. Six injections were made in each mouse with one of the injections being an unmodified alginate control. Injection volumes were 100 µl.

**[0146]** On days 1, 3, 7, 14, 21, and 28 post injection, host cell activity in response to the implantation of modified alginates was imaged kinetically using fluorescent whole animal imaging. 24 hours before *in vivo* fluorescence imaging, 2 nmol of ProSense-680 (VisEn Medical, Woburn, MA, excitation wavelength 680 ± 10 nm, emission 700 ± 10 nm) dissolved in 150 µl sterile PBS was injected into the tail vein of each mouse to image cathepsin activity.

**[0147]** *In vivo* fluorescence imaging was performed with an IVIS-Spectrum measurement system (Xenogen, Hopkinton, MA). The animals were maintained under inhaled anesthesia using 1-4% isoflurane in 100% oxygen at a flow rate of 2.5 L/min. A binning of 8 x 8 and a field of view of 13.1 cm were used for imaging. Exposure time and f/stop - the relative size of the opening of the aperture - were optimized for each acquired image. Data were acquired and analyzed using the manufacturer's proprietary Living Image 3.1 software. All images are presented in fluorescence efficiency, which is defined as the ratio of the collected fluorescent intensity to an internal standard of incident intensity at the selected imaging configuration. Regions of interest (ROIs) were designated around the site of each injection.

**[0148]** Biocompatibility of the materials was examined 14 days post injection. The fluorescence intensity measured at the implantation site of modified alginates was compared with the fluorescence intensity measured at the implantation site of and unmodified alginates. Modified alginates exhibiting a smaller fluorescence intensity at the implantation site than the fluorescence intensity measured at the implantation site of an unmodified alginates were characterized as biocompatible. Modified alginates exhibiting a greater fluorescence intensity at the implantation site than the fluorescence intensity measured at the implantation site of an unmodified alginates were characterized as not biocompatible.

**[0149]** The *in vivo* stability of the alginate gels was assessed at 28 days post injection. Modified alginates which remained at the site of injection after 28 days were characterized as capable of forming mechanically stable hydrogels *in vivo*. Modified alginates which were not present at the site of injection after 28 days were deemed to not capable of



forming mechanically stable hydrogels *in vivo*, and were classified as 'failures'.

**[0150]** Modified alginates characterized as both biocompatible and capable of forming mechanically stable hydrogels *in vivo* were identified as 'hits', and selected for further study.

## 2. Validation of the high throughput *in vivo* screening protocol

**[0151]** In order to validate the high throughput *in vivo* screening assay described above, modified alginates were subcutaneously injected into mice in an array format and crosslinked *in situ* as described above. Mice were imaged on days 1, 3, 7, 14, 21, and 28 post injection using fluorescent whole animal imaging, and tissue samples were collected after imaging for histological analysis. To obtain tissue samples for histological analysis, mice were euthanized via CO<sub>2</sub> asphyxiation and the injected biomaterial and surrounding tissue were excised. The tissues were then fixed in 10% formalin, embedded in paraffin, cut into 5 µm sections, and stained using hematoxylin and eosin (H&E) for histological analysis by a board certified pathologist.

**[0152]** Fibrosis was rated on a scale where a zero involved no fibrosis, a one indicated partial coverage with one to two layers of fibrosis, a two is designated a thicker fibrotic layer that nearly covered the implant, and a three denoted concentric fibrotic coverage of the polymer. Both polymorphonuclear (PMN) cells and macrophages were rated on a scale where no observed cells were indicated with a zero, scattered cells scored a one, numerous cells clustering on the sides of the polymer scored a two, and numerous cells surrounding the material resulted in a three. Both the histological score and fluorescence response normalized to alginate were examined for the whole library and materials that outperformed unmodified alginate were judged to be biocompatible. This corresponds to a normalized fluorescent signal of <100% and a fibrosis score of <3.

**[0153]** Data captured using whole animal imaging was demonstrated to displayed similar temporal trends in cellular recruitment of phagocytes to the biomaterials compared to histological analysis. Accordingly, the high throughput *in vivo* screening method described above was validated.

### Example 5: *In vivo* screening of modified alginates to quantify biocompatibility

**[0154]** 8-12 week old male SKH1 mice were obtained from Charles River Laboratories (Wilmington, MA). The mice were maintained at the animal facilities of Massachusetts Institute of Technology, accredited by the American Association of Laboratory Animal care, and were housed under standard conditions with a 12-hour light/dark cycle. Both water and food were provided *ad libitum*.

**[0155]** Injections were performed in accordance with ISO 10993-6: 2001. Prior to injection all materials were sterilized via 0.22 µm filtration. The mice were anesthetized via isoflurane inhalation at a concentration of 1-4% isoflurane/balance O<sub>2</sub> to minimize movement. Their backs were scrubbed with 70% isopropyl alcohol and the animals were injected with a modified alginate. The injection volume was 100 µl.

**[0156]** Cathepsin activity was measured 7 days post injection using an *in vivo* fluorescence assay to quantify the foreign body response to the modified alginate. 24 hours before *in vivo* fluorescence imaging, 2 nmol of ProSense-680 (VisEn Medical, Woburn, MA, excitation wavelength 680 ± 10 nm, emission 700 ± 10 nm) dissolved in 150 µl sterile PBS was injected into the tail vein of each mouse to image cathepsin activity.

**[0157]** *In vivo* fluorescence imaging was performed with an IVIS-Spectrum measurement system (Xenogen, Hopkinton, MA). The animals were maintained under inhaled anesthesia using 1-4% isoflurane in 100% oxygen at a flow rate of 2.5 L/min. A binning of 8 x 8 and a field of view of 13.1 cm were used for imaging. Exposure time and f/stop - the relative size of the opening of the aperture - were optimized for each acquired image. Data were acquired and analyzed using the manufacturer's proprietary Living Image 3.1 software. All images are presented in fluorescence efficiency, which is defined as the ratio of the collected fluorescent intensity to an internal standard of incident intensity at the selected imaging configuration. Regions of interest (ROIs) were designated around the site of each injection.

**[0158]** Fluorescence images were captured 7 days post-injection illustrating relative cathepsin activity at the point of injection of selected modified alginates. The fluorescence intensity was measured and normalized to the fluorescence response measured using unmodified alginate in order to quantify the biocompatibility of the modified alginates. The results obtained for selected modified alginates are included in Figure 4.

### Example 6: Treatment of diabetes in STZ-induced diabetic mice (Reference only)

**[0159]** The transplantation of biocompatible alginate-encapsulated beta cells offers potential as a treatment for diabetes. Pancreatic rat islet cells were encapsulated using fourteen biocompatible modified alginate polymers identified using the assays detailed above (including PF\_N287\_B\_B4, PF\_N287\_F2, PF\_N287\_G3, PF\_N287\_B3, PF\_N287\_B\_B8, PF\_N287\_A4, PF\_N287\_B1, PF\_N287\_E3, PF\_N263\_C12, PF\_N63\_A12, PF\_N287\_E1, PF\_N287\_D3, PF\_N263\_A7, and PF\_N263\_C6). Alginate-encapsulated islets capsules were fabricated from 750µl of

a 4% (w/v) solution of each modified alginate in deionized water containing suspended 1,000 islets suspended using the Inotech encapsulator (Inotech) set to a voltage of 1.05kV, a vibration of 1225Hz, and a flow rate of 10-25 ml/min with a 300 $\mu$ m nozzle. Alginate was crosslinked in a 20mM BaCl<sub>2</sub> solution. After encapsulation, the capsules were washed twice with HEPES solution, four times with Krebs solution, and twice with RPMI-1640 medium.

**[0160]** The encapsulated rat islet cells were transplanted into STZ induced diabetic mice. Prior to transplantation, the mice were anesthetized under continuous flow of 1-4% isoflurane with oxygen at 0.5L/min. A shaver with size #40 clipper blade will be used to remove hair to reveal an area of about 2cm x 2cm on ventral midline of the animal abdomen. The entire shaved area was aseptically prepared with a minimum of 3 cycles of scrubbing with povidine, followed by rinsing with 70% alcohol. A final skin paint with povidine was also applied. The surgical site was draped with sterile disposable paper to exclude surrounding hair from touching the surgical site. A sharp surgical blade was used to cut a 0.5-0.75cm midline incision through the skin and the linea alba into the abdomen. A sterile plastic pipette was used to transfer the alginate microcapsules into the peritoneal cavity. The abdominal muscle was closed by suturing with 5-0 Ethicon black silk or PDS-absorbable 5.0-6.0 monofilament absorbable thread. The external skin layer was closed using wound clips. These wound clips were removed 7-10d postsurgery after complete healing was confirmed.

**[0161]** Blood glucose levels in the STZ induced diabetic mice were monitored daily for between 20 and 30 days post-transplantation using a drop of blood obtained by scrubbing the tail with 70% isopropyl alcohol and making a superficial cut on the skin of the tail to produce a drop of blood. Mice were restrained during sampling in a rotating tail injector.

**[0162]** The blood glucose levels in the STZ induced diabetic mice following islet transplantation are shown in Figure 5. The dashed black line represents normoglycemia in mice. Pancreatic rat islet cells were encapsulated in modified alginates were able to reduce the blood glucose levels in all cases, and in some cases, were even able to induce normoglycemia.

#### Example 7. Particles prepared from mixture of modified alginate(s) and unmodified alginate (Reference only)

**[0163]** The growing recognition of the parameters driving fibrosis *in vivo* has been applied to the analysis of the performance of modified alginates. Intraperitoneal (IP) implantation of modified alginate capsules revealed that modified alginates may result in abnormally shaped capsules when crosslinked using conditions defined for unmodified alginates. These abnormally shaped capsules can complicate implementation and interpretation of modified alginate capsules implanted IP. In an effort to improve the capsule morphology, formulation methods for use with modified alginate micro-particles were developed where modified alginates were blended with a small amount of high molecular weight alginate. Particles prepared from this mixture yielded particles with improved morphology and stability.


**[0164]** A 6% solution of modified alginate (w/w) was combined 1:1 by volume with a 1.15% solution of unmodified alginate (w/w). After mixing, capsules are formed by following this solution through an electrostatic droplet generator, followed by crosslinking of the polymer in a 20mM aqueous barium chloride solution.

**[0165]** Particles prepared from modified alginate 263\_A12 microparticles formulated with barium and mannitol were compared to particles prepared from 263\_A12 blended with a small amount of unmodified SLG100 alginate (16% by weight). The particles prepared from a mixture of modified alginate and unmodified alginate produced more homogenous microparticle populations. Quantitative fluorescence analysis with prosense at several time points with modified alginates blended with SLG100 was performed. The results are shown in Figure 6. Several reformulated modified alginates displayed less inflammatory response at day 7 compared to the control alginate. Initial experiments with large capsules (1.5 mm diameter) show comparably clean capsules after 2 weeks in the IP space of immunocompetent C57BL6 mice.

**[0166]** Data collected to date with these controlled capsules indicates that reformulation and capsule morphology can have a significant effect on inflammation as measured by prosense. An improved inflammation response is observed in some polymers (Figure 6), while others are impacted negatively.

#### Claims

1. A singularly modified alginate comprising one or more covalently modified monomers defined by Formula I



Formula I


wherein

X is NR,

R<sub>1</sub> includes a 1,2,3-triazole ring, or an alkyne group;

Y<sub>1</sub> and Y<sub>2</sub> independently are hydrogen or -PO(OR)<sub>2</sub> or

Y<sub>2</sub> is absent, and Y<sub>2</sub> together with the two oxygen atoms to which Y<sub>1</sub> and Y<sub>2</sub> are attached form a cyclic structure as shown below



and

R<sub>2</sub> and R<sub>3</sub> are, independently, hydrogen, alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, alkoxy, substituted alkoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, arylthio, substituted arylthio, carbonyl, substituted carbonyl, carboxyl, substituted carboxyl, amino, substituted amino, amido, substituted amido, polyaryl, substituted polyaryl, C<sub>3</sub>-C<sub>20</sub> cyclic, substituted C<sub>3</sub>-C<sub>20</sub> cyclic, heterocyclic, substituted heterocyclic, amino acid, poly(ethylene glycol), peptide, or polypeptide group;


or

R<sub>2</sub> and R<sub>3</sub>, together with the carbon atom to which they are attached, form a 3- to 8-membered unsubstituted or substituted carbocyclic or heterocyclic ring; and


R is, independently for each occurrence, hydrogen, alkyl, substituted alkyl, alkenyl, substituted alkenyl, alkynyl, substituted alkynyl, aryl, substituted aryl, heteroaryl, substituted heteroaryl, alkoxy, substituted alkoxy, aroxy, substituted aroxy, alkylthio, substituted alkylthio, arylthio, substituted arylthio, polyaryl, substituted polyaryl, C<sub>3</sub>-C<sub>20</sub> cyclic, substituted C<sub>3</sub>-C<sub>20</sub> cyclic, heterocyclic, substituted heterocyclic, amino acid, poly(ethylene glycol), peptide, or polypeptide group.

2. The modified alginate of claim 1, wherein Y<sub>1</sub> and Y<sub>2</sub> are each hydrogen and X is NH
3. The modified alginate of claim 1 or 2, wherein R<sub>1</sub> comprises a 1,2,3-triazole ring obtained by an 1,3-dipolar cycloaddition reaction wherein a first molecule containing an azide moiety is reacted with a second molecule containing a terminal or internal alkyne.
4. The modified alginate of claim 3, wherein the alkyne in the 1,3-dipolar cycloaddition is selected from:


5




10



15



20




5. The modified alginate of any one of claims 3 to 4, wherein

25


R<sub>1</sub> is

30



R<sub>4</sub> is

35



40


and wherein Y<sub>1</sub> and Y<sub>2</sub> are each hydrogen and X is NH .

6. The modified alginate of any one of claims 3 to 5, wherein

45


R<sub>1</sub> is

50




and R<sub>4</sub> is

55




and wherein  $Y_1$  and  $Y_2$  are each hydrogen and X is NH.


7. The modified alginate according to any one of claims 3 to 6, wherein said monomer is defined by Formula E



or Formula F




wherein X1 is derived from an alkyne selected from:



5

10



15

20

25

30

35

8. The modified alginate of any one of claims 3 to 7, wherein more than 20% of the monomers in the modified alginate comprise covalently modified monomers.
9. The modified alginate of any one of claims 3 to 8, wherein the modified alginate has a weight average molecular weight between about 10,000 Da and 500,000 Da.
10. A hydrogel comprising a modified alginate according to any one of claims 3 to 9, wherein the modified alginate can be ionically crosslinked using  $\text{Ca}^{2+}$ ,  $\text{Ba}^{2+}$ , or  $\text{Sr}^{2+}$ .
11. The hydrogel of claim 10, further comprising a polymer selected from the group consisting of poly (ethylene glycol), chitosan, dextran, hyaluronic acid, silk, fibrin, poly(vinyl alcohol), and poly(hydroxyl ethyl methacrylate).
12. Biological material encapsulated with a hydrogel according to claim 10 or 11, whereby the encapsulated material is for implanting or transplanting into a human or animal patient to treat a disease or disorder in the human or animal patient.
13. The biological material according to claim 12, wherein the hydrogel comprises a microcapsule.
14. The biological material according to claim 12 or 13, wherein the hydrogel comprises a mixture of the modified alginate and an unmodified alginate.
15. The biological material of any one of claims 12 to 14, wherein the biological material is cells.


## Patentansprüche

40

1. Einfach modifiziertes Alginat, umfassend ein oder mehrere kovalent modifizierte Monomere, definiert durch Formel I

45

50



Formel I


55

worin

X NR ist,  
 $\text{R}_1$  einen 1,2,3-Triazolring oder eine Alkin-Gruppe einschließt;

$Y_1$  und  $Y_2$  unabhängig Wasserstoff oder  $-PO(OR)_2$  sind oder

$Y_2$  fehlt und  $Y_2$  zusammen mit den beiden Sauerstoffatomen, an die  $Y_1$  und  $Y_2$  gebunden sind, eine im Folgenden dargestellte cyclische Struktur bildet



und

$R_2$  und  $R_3$  unabhängig Wasserstoff, Alkyl, substituiertes Alkyl, Alkenyl, substituiertes Alkenyl, Alkynyl, substituiertes Alkynyl, Aryl, substituiertes Aryl, Heteroaryl, substituiertes Heteroaryl, Alkoxy, substituiertes Alkoxy, Aroxy, substituiertes Aroxy, Alkylthio, substituiertes Alkylthio, Arylthio, substituiertes Arylthio, Carbonyl, substituiertes Carbonyl, Carboxyl, substituiertes Carboxyl, Amino, substituiertes Amino, Amido, substituiertes Amido, Polyaryl, substituiertes Polyaryl,  $C_3$ - $C_{20}$ -Cyclus, substituierter  $C_3$ - $C_{20}$ -Cyclus, Heterocyclus, substituierter Heterocyclus, Aminosäure, Poly(ethylenglykol), Peptid oder eine Polypeptidgruppe sind;

oder


$R_2$  und  $R_3$  zusammen mit dem Kohlenstoffatom, an das sie gebunden sind, einen 3- bis 8-gliedrigen unsubstituierten oder substituierten carbocyclischen oder heterocyclischen Ring bilden; und


$R$  unabhängig für jedes Vorkommen Wasserstoff, Alkyl, substituiertes Alkyl, Alkenyl, substituiertes Alkenyl, Alkynyl, substituiertes Alkynyl, Aryl, substituiertes Aryl, Heteroaryl, substituiertes Heteroaryl, Alkoxy, substituiertes Alkoxy, Aroxy, substituiertes Aroxy, Alkylthio, substituiertes Alkylthio, Arylthio, substituiertes Arylthio, Polyaryl, substituiertes Polyaryl,  $C_3$ - $C_{20}$ -Cyclus, substituierter  $C_3$ - $C_{20}$ -Cyclus, Heterocyclus, substituierter Heterocyclus, Aminosäure, Poly(ethylenglykol), Peptid oder eine Polypeptidgruppe ist.

2. Modifiziertes Alginat gemäß Anspruch 1, wobei  $Y_1$  und  $Y_2$  jeweils Wasserstoff sind und  $X$  NH ist.

3. Modifiziertes Alginat gemäß Anspruch 1 oder 2, wobei  $R_1$  einen 1,2,3-Triazolring umfasst, der durch eine 1,3-dipolare Cycloadditionsreaktion erhalten wird, bei der ein erstes Molekül, das eine Azideinheit enthält, mit einem zweiten Molekül, das ein terminales oder internes Alkin enthält, umgesetzt wird.


4. Modifiziertes Alginat gemäß Anspruch 3, wobei das Alkin in der 1,3-dipolaren Cycloaddition ausgewählt ist aus:






5. Modifiziertes Alginat gemäß mindestens einem der Ansprüche 3 bis 4, wobei

$R_1$




ist;  
 $R_4$




ist;  
und worin  $Y_1$  und  $Y_2$  jeweils Wasserstoff sind und X NH ist.

6. Modifiziertes Alginat gemäß mindestens einem der Ansprüche 3 bis 5, wobei

$R_1$




ist;  
und  $R_4$




ist;  
und worin  $Y_1$  und  $Y_2$  jeweils Wasserstoff sind und X NH ist.




7. Modifiziertes Alginat gemäß mindestens einem der Ansprüche 3 bis 6, wobei das Monomer definiert ist durch die Formel E




oder Formel F



worin X<sub>1</sub> von einem Alkin abgeleitet ist, das ausgewählt ist aus:






8. Modifiziertes Alginat gemäß mindestens einem der Ansprüche 3 bis 7, wobei mehr als 20% der Monomere in dem modifizierten Alginat kovalent modifizierte Monomere umfassen.
9. Modifiziertes Alginat gemäß mindestens einem der Ansprüche 3 bis 8, wobei das modifizierte Alginat ein gewichtsgemittelter Molekulargewicht zwischen etwa 10.000 Da und 500.000 Da aufweist.
10. Hydrogel, umfassend ein modifiziertes Alginat gemäß mindestens einem der Ansprüche 3 bis 9, wobei das modifizierte Alginat unter Verwendung von  $\text{Ca}^{2+}$ ,  $\text{Ba}^{2+}$  oder  $\text{Sr}^{2+}$  ionisch vernetzt werden kann.
11. Hydrogel gemäß Anspruch 10, ferner umfassend ein Polymer, das ausgewählt ist aus einer Gruppe bestehend aus Poly(ethylenglykol), Chitosan, Dextran, Hyaluronsäure, Seide, Fibrin, Poly(vinylalkohol) und Poly(hydroxyethylmethacrylat).
12. Biologisches Material, das mit einem Hydrogel gemäß Anspruch 10 oder 11 eingekapselt ist, wobei das eingekapselte Material zur Implantation oder Transplantation in einen menschlichen oder tierischen Patienten bestimmt ist, um eine Krankheit oder Störung bei dem menschlichen oder tierischen Patienten zu behandeln.
13. Biologisches Material gemäß Anspruch 12, wobei das Hydrogel eine Mikrokapsel umfasst.
14. Biologisches Material gemäß Anspruch 12 oder 13, wobei das Hydrogel eine Mischung aus dem modifizierten Alginat und einem nicht-modifizierten Alginat umfasst.
15. Biologisches Material gemäß mindestens einem der Ansprüche 12 bis 14, wobei das biologische Material Zellen ist.

## Revendications

1. Alginate à modification singulière comprenant un ou plusieurs monomères modifiés par covalence définis par la Formule I



Formule I


dans lequel

X est NR,

$R_1$  inclut un cycle 1,2,3-triazole ou un groupe alcyne ;

$Y_1$  et  $Y_2$  sont indépendamment de l'hydrogène ou  $-\text{PO}(\text{OR})_2$  ou

$Y_2$  est absent, et  $Y_2$  conjointement avec les deux atomes d'oxygène auxquels  $Y_1$  et  $Y_2$  sont fixés, forme une structure cyclique telle qu'indiquée ci-dessous



et


$R_2$  et  $R_3$  sont, indépendamment, un groupe hydrogène, alkyle, alkyle substitué, alcényle, alcényle substitué, alcynyle, alcynyle substitué, aryle, aryle substitué, hétéroaryle, hétéroaryle substitué, alcoxy, alcoxy substitué, aroxy, aroxy substitué, alkylthio, alkylthio substitué, arylthio, arylthio substitué, carbonyle, carbonyle substitué, carboxyle, carboxyle substitué, amino, amino substitué, amido, amido substitué, polyaryle, polyaryle substitué, cyclique en  $C_3$ - $C_{20}$ , cyclique substitué en  $C_3$ - $C_{20}$ , hétérocyclique, hétérocyclique substitué, acide aminé, poly(éthylène glycol), peptide ou polypeptide ;


ou

$R_2$  et  $R_3$ , conjointement avec l'atome de carbone auquel ils sont fixés, forment un cycle carbocyclique ou hétérocyclique non substitué ou substitué de 3 à 8 chaînons ; et

$R$  est, indépendamment pour chaque occurrence, un groupe hydrogène, alkyle, alkyle substitué, alcényle, alcényle substitué, alcynyle, alcynyle substitué, aryle, aryle substitué, hétéroaryle, hétéroaryle substitué, alcoxy, alcoxy substitué, aroxy, aroxy substitué, alkylthio, alkylthio substitué, arylthio, arylthio substitué, polyaryle, polyaryle substitué, cyclique en  $C_3$ - $C_{20}$ , cyclique substitué en  $C_3$ - $C_{20}$ , hétérocyclique, hétérocyclique substitué, acide aminé, poly(éthylène glycol), peptide ou polypeptide.


2. Alginate modifié selon la revendication 1, dans lequel  $Y_1$  et  $Y_2$  sont chacun de l'hydrogène et  $X$  est NH.
3. Alginate modifié selon la revendication 1 ou 2, dans lequel  $R_1$  comprend un cycle 1,2,3-triazole obtenu par une réaction de cycloaddition 1,3-dipolaire, dans lequel une première molécule contenant un fragment azide est mise à réagir avec une seconde molécule contenant un alcyne terminal ou interne.
4. Alginate modifié selon la revendication 3, dans lequel l'alcyne dans la cycloaddition 1,3-dipolaire est choisi parmi :






5. Alginate modifié selon l'une quelconque des revendications 3 à 4, dans lequel

$R_1$  est




$R_4$  est




et dans lequel  $Y_1$  et  $Y_2$  sont chacun de l'hydrogène et X est NH.

6. Alginate modifié selon l'une quelconque des revendications 3 à 5, dans lequel

$R_1$  est




$R_4$  est




et dans lequel  $Y_1$  et  $Y_2$  sont chacun de l'hydrogène et X est NH.


7. Alginate modifié selon l'une quelconque des revendications 3 à 6, dans lequel ledit monomère est défini par la formule E



ou la Formule F



dans lequel  $X_1$  est dérivé d'un alcyne choisi parmi :



8. Alginate modifié selon l'une quelconque des revendications 3 à 7, dans lequel plus de 20 % des monomères dans l'alginate modifié comprennent des monomères modifiés par covalence.
9. Alginate modifié selon l'une quelconque des revendications 3 à 8, dans lequel l'alginate modifié présente un poids

moléculaire moyen en poids entre environ 10 000 Da et 500 000 Da.

**10.** Hydrogel comprenant un alginate modifié selon l'une quelconque des revendications 3 à 9, dans lequel l'alginate modifié peut être réticulé ioniquement en utilisant  $\text{Ca}^{2+}$ ,  $\text{Ba}^{2+}$  ou  $\text{Sr}^{2+}$ .

**11.** Hydrogel selon la revendication 10, comprenant en outre un polymère choisi dans le groupe consistant en poly (éthylène glycol), chitosane, dextrane, acide hyaluronique, soie, fibrine, alcool poly(vinyle) et poly(méthacrylate d'hydroxyéthyle).


**12.** Matériau biologique encapsulé avec un hydrogel selon la revendication 10 ou 11, selon lequel le matériau encapsulé est destiné à être implanté ou transplanté chez un patient humain ou animal pour traiter une maladie ou un trouble chez le patient humain ou animal.

**13.** Matériau biologique selon la revendication 12, dans lequel l'hydrogel comprend une microcapsule.

**14.** Matériau biologique selon la revendication 12 ou 13, dans lequel l'hydrogel comprend un mélange de l'alginate modifié et d'un alginate non modifié.

**15.** Matériau biologique selon l'une quelconque des revendications 12 à 14, dans lequel le matériau biologique est des cellules.

FIG. 1






FIG. 2






FIG. 3




FIG. 4




FIG. 5




FIG. 6

## REFERENCES CITED IN THE DESCRIPTION

*This list of references cited by the applicant is for the reader's convenience only. It does not form part of the European patent document. Even though great care has been taken in compiling the references, errors or omissions cannot be excluded and the EPO disclaims all liability in this regard.*

### Patent documents cited in the description

- US 4352883 A, Lim [0002] [0110]
- US 7807150 B, Vacanti [0003]
- US 6129761 A, Hubbell [0004]
- US 6060053 A [0006]
- US 20080242738 A [0008]
- GB 768309 A [0008]
- US 5622718 A [0008]
- US 2881161 A [0008]
- EP 1614696 A [0008]

### Non-patent literature cited in the description

- LIM, F. ; SUN, A. M. *Science*, 1980, vol. 210, 908-910 [0002]
- AEBISCHER et al. *J Biomech Eng.*, May 1991, vol. 113 (2), 178-83 [0004]
- Lesney *Modern Drug Discovery*, 2001, vol. 4 (3), 45-50 [0004]
- ELLIOT, R. B. et al. *Xenotransplantation*, 2007, vol. 14 (2), 157-161 [0005]
- YANG et al. *Carbohydrate Polymers*, 2011, vol. 84, 33-39 [0008]
- MOSES, J.E. ; MOORHOUSE, A.D. *Chem Soc. Rev.*, 2007, vol. 36, 1249-1262 [0037]
- KOLB, H.C. ; SHARPLESS, K.B. *Drug Discovery Today.*, 2003, vol. 8 (24), 1128-1137 [0037]
- KOLB, H.C. et al. *Angew. Chem. Int. Ed.*, 2001, vol. 40, 2004-2021 [0037]
- MARCH. *Advanced Organic Chemistry*. Wiley-Interscience Publication, 2001 [0071]
- STOWELL, J. K. ; WIDLANSKI, T. S. *Tetrahedron Lett.*, 1995, vol. 36 (11), 1825-1826 [0085]
- DE VOS, P et al. *Biomaterials*, 2006, vol. 27, 5603-5617 [0087]